

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT.

SALEM, OREGON 97310

within 30 days from the date

of well completion.

RECEIVED WATER WELL REPORT

STATE OF OREGON

AUG 4 1980

(Please type or print)

WATER RESOURCES DEPT

SALEM, OREGON

GILL...7/1

State Well No.

15/20E-23da

State Permit No.

(1) OWNER:

Name Joseph D'AlberaAddress Box 17Mikkalo, Oregon 97861

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
☐ Jetted ☐
 L ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
 Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

12" Diam. from +1 ft. to 21 ft. Gage 250
 " Diam. from _____ ft. to _____ ft. Gage _____
 " Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in. by	in.
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

" " " " " "

" " " " " "

a pump test 1400 gal./min. with 250 ft. drawdown after 1 hrs.

Artesian flow _____ g.p.m.

Temperature of water _____ Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used CementWell sealed from land surface to 20 ft.Diameter of well bore to bottom of seal 16 in.Diameter of well bore below seal 12 in.Number of sacks of cement used in well seal 16 sacksHow was cement grout placed? Placed by tremie pipe from bottom to top of oversized drill holeWas a drive shoe used? ☐ Yes ☐ No Plugs _____ Size: location _____ ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Gilliam Driller's well number _____N.E. 1/4 SE 1/4 Section 23 T. 18. R. 20E. W.M.

Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 120 ft.Static level 120 ft. below land surface. Date 7-16-80

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 12"Depth drilled 375 ft. Depth of completed well 375 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil	0	8	
Claystone, brown	8	14	
Rock, black	14	28	
Basalt	28	45	
Rock, light brown	45	50	
Basalt	50	73	
Rock, med. black	73	81	
Basalt	81	115	
Basalt, hard, gray	115	183	
Rock, med. black, quartz claystone	183	204	W.B.
Rock, black	204	265	
Basalt, hard, gray	265	298	
Rock, med. black, blue claystone	298	314	W.B.
Basalt	314	342	
Rock, brown & yellow claystone	342	348	
Basalt	348	359	
Rock, broken, brown	359	371	W.B.
Basalt	371	375	

Work started 7-2 1980 Completed 7-16 1980Date well drilling machine moved off of well 7-16 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] James T. Leitch Date 7-16, 1980
(Drilling Machine Operator)Drilling Machine Operator's License No. 665

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name TROY GRIFFIN
(Person, firm or corporation) (Type or print)Address 900 HERMISTON AVE. HERMISTON ORE[Signed] Troy Griffin
(Water Well Contractor)Contractor's License No. 65 Date 7-16, 1980