

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT

SALEM, OREGON 97310

within 30 days from the date

of well completion.

RECEIVED

WATER WELL REPORT

STATE OF OREGON

AUG 4 1980

(Please type or print)

GILL... 73

State Well No. 15/20E-2600

State Permit No.

WATER RESOURCES DEPT

SALEM, OREGON

(1) OWNER:

Name Joseph D'AlbinoAddress BL 17
Mikkalo, Oregon 97861

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
☐ Jetted ☐
L ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
12" Diam. from +1 ft. to 23 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in. by	in.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

AR test 800 gal./min. with 190 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 23 ft.

Diameter of well bore to bottom of seal 16 in.

Diameter of well bore below seal 12 in.

Number of sacks of cement used in well seal 20 sacks

How was cement grout placed? Thru pipe from bottom to top of uncased drill hole.Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Willamette Driller's well number

N. E 1/4. S. W 1/4 Section 26 T. 18. R. 20 E. W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 318 ft.

Static level 280 ft. below land surface. Date 7-1-80

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 10"

Depth drilled 475 ft. Depth of completed well 475 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil	0	5	
Claystone, gray	5	13	
Basalt	13	16	
Rock, spt. brown	16	20	
Basalt	20	68	
Rock, med. black	68	162	
Basalt	162	168	
Rock, med. black	168	206	
Basalt	206	238	
Rock, med. black	238	289	
Basalt	289	318	
Rock, light brown/yellow claystone	318	357	
Basalt	357	365	
Rock, brown/yellow claystone	365	378	
Basalt, hard, gray	378	425	
Rock, brown/yellow clay.	425	448	W.B.
Rock, med. black	448	461	
Basalt	461	475	

Work started 6-23 1980 Completed 7-1 1980

Date well drilling machine moved off of well 7-1 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] James T. Litch Date 7-10, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 665

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name TROY GRIFFIN
(Person, firm or corporation) (Type or print)Address 900 HERMISTON AVE, HERMISTON ORE[Signed] Troy Griffin
(Water Well Contractor)

Contractor's License No. 65 Date 7-10, 1980