

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON (Please type or print)

GRAN...164

State Well No. 11/29-11

G-3696

State Permit No.

(1) OWNER:

Name Ivan Simmons
Address 174. Vernon, Ore.

(2) LOCATION OF WELL:

County Grant Driller's well number
SW 1/4 SE 1/4 Section 11 T. 11S R. 29E. W.M.
Bearing and distance from section or subdivision corner
1/4 mile and 190' west from the SE corner, thence North 9'

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
 abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 120 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used cutting torch
Size of perforations 6 in. by 3/8 in.
40 perforations from 120 ft. to ft.
perforations from 40 ft. to 120 ft.
perforations from ft. to ft.
perforations from 3 per ft. ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Model No.
Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Commercial Mud
Depth of seal 30 ft. Was a packer used? no
Diameter of well bore to bottom of seal 8 1/2 in.
Were any loose strata cemented off? ☐ Yes ☐ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☐ No
Type of water? Depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 10 ft. below land surface Date 8, 15, 66
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? Columbia

Yield: 200 gal./min. with 120 ft. drawdown after 6 hrs.

" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 50 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 6 in
Depth drilled 370 ft. Depth of completed well 370 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top soil	0	4
Clay grey to 40 ft	4	40
dark stone some water	40	100
grey shale real soft	100	115
dark stone	115	280
shale grey real tuff	280	330
clay with pea gravel	330	370

This seems to be considerable water in this area at shallow depths.

Work started Aug 9 1966 Completed Aug 15 1966

Date well drilling machine moved off of well Aug 15 1966

(13) PUMP:

Manufacturer's Name Western when installed
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME ROY T FRENCH (Person, firm or corporation) (Type or print)

Address 1015 SW. 7th Ave. Pendleton Ore

Drilling Machine Operator's License No. 209

[Signed] Roy T French (Water Well Contractor)

Contractor's License No. 107 Date Aug 16 1966