

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

GRAN.....

State Well No. 115/29E-12ac

State Permit No.

(1) OWNER:

Name Bud Trowbridge
Address Fox O.R.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from 1 ft. to 360 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in. by	in.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

d: 500 gal./min. with 80 ft. drawdown after 3 hrs.
" compressor " " "
" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow 34 g.p.m.

Temperature of water 70° Depth artesian flow encountered 365 ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT
Well sealed from land surface to 355 ft.
Diameter of well bore to bottom of seal 12 in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 200 sacks
How was cement grout placed? Pumped
Through pipe

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Grant Driller's well number F-80-1
SW 1/4 NE 1/4 Section 62 T. 11S R. 29E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 370 ft.

Static level 0 ft. below land surface. Date 2-12-80

Artesian pressure 10 lbs. per square inch. Date 2-12-80

(12) WELL LOG:

Diameter of well below casing 8

Depth drilled 470 ft. Depth of completed well 470 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL 3 in.	0	1	
CLAY Brn. med	1	50	
CLAY Grey med	50	150	
SANDY CLAY Grey	150	350	
CLAY Grey HARD	350	365	
SAND BIK. med	365	370	0-
CLAY TAN med	370	390	
GRANIT Frag. Grey	390	395	
GRANIT Grey HARD	395	400	
BASALT BIK. HARD	400	410	
GREEN STONE HARD	410	460	
CLAY Red SOFT	460	470	

RECEIVED

MAR 12 1980

WATER RESOURCES DEPT
SALEM, OREGON

Work started 10 Dec 1979 Completed 11 Feb 1980

Date well drilling machine moved off of well 12 Feb 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Francis R. Rupp Date 9 Mar 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1185

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Uobe Drilling, Inc.
(Person, firm or corporation) (Type or print)

Address Medford City, Oregon

[Signed] Bond John
(Water Well Contractor)

Contractor's License No. 582 Date 3-10, 1980