

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

WATER WELL REPORT

GRAN. 2432 STATE OF OREGON AUG 1 1974

(Please type or print)

STATE ENGINEER
SALEM, OREGON

State Well No. 135/26E-1a

State Permit No.

(1) OWNER:

Name City of Dayville
Address Dayville, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☒
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

16" Diam. from 0 ft. to 30 ft. Gage 250

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

pe of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "
" " " "

Ballor test gal./min. with ft. drawdown after hrs.

Artesian flow 1 g.p.m.

Temperature of water Depth artesian flow encountered 418 ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 30 ft.

Diameter of well bore to bottom of seal 25 20 in.

Diameter of well bore below seal 7-7/8 in. to 175, 6" to bottom

Number of sacks of cement used in well seal 25 sacks

Number of sacks of bentonite used in well seal 0 sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Grant Driller's well number
1/4 NE 1/4 Section 1 T. 13 S R. 26 E. W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 418 ft.

Static level ft. below land surface. Date

Artesian pressure 8 ± lbs. per square inch. Date 7/18/74

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 609 ft. Depth of completed well -0- ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil	0	2 1/2	
Gravel	2 1/2	19	
Gray clay	19	37	
Brown silt	37	42	
Gray clay w/basalt chips	42	75	
Gray & brown clay	75	418	
Silty clay	418	425	46 gpm
Gray clay	425	609	

WELL ABANDONED - Cleaned out bridge
from 127 to 170 feet, installed 1-1/4" pipe to 600 ft. Pumped 157 sacks of cement from 600 ft. to 10 ft below surface.

Work started May 21, 1973 Completed 7/23 19 74

Date well drilling machine moved off of well 7/23/74 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Steve M. Jensen Date 7/29/74, 19

(Drilling Machine Operator)

Drilling Machine Operator's License No. 235

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name PROJECT: Corporation (Type or print)

Address 21075 S.W. Tualatin Valley Hwy, Aloha, Or. (Type or print)

[Signed] Steve M. Jensen (Water Well Contractor)

Contractor's License No. 79 Date 7/29/74, 19