

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

WELL I.D. # L

23641

START CARD #

107391

(1) OWNER:

Well Number

2

Name

LANCE BARKER

Address

HC 84 Box 632

City

CANYON CO.

State

OR

Zip

97780

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation

☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 158 ft.Explosives used ☐ Yes ☒ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
14	0	18	BENTONITE	0	18	13
8	18	158				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other Packed

Backfill placed from ft. to ft. Material 3/8 Bentonite

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8	0	18	.25	☒	☐	☐	☐
Liner: 6.36	5	158		☒	☐	☒	☐

Final location of shoe(s) N/A

(7) PERFORATIONS/SCREENS:

☒ Perforations Method FACTOR CUT 1/8"
☐ Screens Type 5 pipe Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
118	158	1/8	5	6"		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
120	100%	158	1 hr.

Temperature of water 55 Depth Artesian Flow Found 73

Was a water analysis done? ☐ Yes By whomDid any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County LYNN Latitude LongitudeTownship 15 N or S Range 30 E or W. WM.Section 26 SE 1/4 NW 1/4Tax Lot 415 Lot 1 Block Subdivision

Street Address of Well (or nearest address)

(10) STATIC WATER LEVEL:

34 ft. below land surface.

Date 19 Nov 2000

Artesian pressure lb. per square inch.

Date

(11) WATER BEARING ZONES:

Depth at which water was first found

73

From	To	Estimated Flow Rate	SWL
73	158		

(12) WELL LOG:

Ground Elevation 5227

Material	From	To	SWL
TOP SOIL	0	1	
LIGHT BROWN CLAY	1	37	
RED CLAY with sand	37	158	
GRAVELS			

RECEIVED

NOV 29 2000

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 18 Nov 2000 Completed 19 Nov 2000

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number

Signed Date