

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 67667
START CARD # 169197

Instructions for completing this report are on the last page of this form.

(1) LANDOWNER Name JACK Simmons Well Number 1
Address 2214 NE 3RD ST.
City PRINEVILLE State OR Zip 97754

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Other

(4) PROPOSED USE
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 150 ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
10	0	38	BENTONITE	0	38	18

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other BURIN METHOD
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

Casing:	Diameter		Gauge	Steel	Plastic	Welded	Threaded
	From	To					
	10	42	39	25	☐	☐	☐
					☐	☐	☐
					☐	☐	☐
Liner:	5 9/16	10	150	188	☒	☒	☐
					☐	☐	☐
					☐	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None
Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS
☒ Perforations Method FACTORY CUT
☐ Screens Type STEEL Material 188

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
90	130	188	5	5 9/16	20	☐	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
8	100%	198	1.22

Temperature of water 58 Depth Artesian Flow Found 90
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL (legal description)
County GRANT
Tax Lot 213 Lot _____
Township 9 N or S Range 27 E or W WM
Section 14 NE 1/4 NE 1/4

Lat _____ " or _____ (degrees or decimal)
Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) 1.7 miles South on COLONIE RD. MONUMENT OR.


(10) STATIC WATER LEVEL
8 ft. below land surface. Date 25 July 05
_____ ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES
Depth at which water was first found _____

From	To	Estimated Flow Rate	SWL
90	110	8 GPM	8

(12) WELL LOG Ground Elevation _____

Material	From	To	SWL
TOP SOIL	0	30	8
BROWN CLAY + Boulders	30	46	
GRAY CLAY + SAND	46	89	
BROWN CLAY + SAND	89	110	
WITH GRAVELS			
GRAY CLAY + GRAVEL	110	150	



Date Started 6-27-05 Completed 6-28-05

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1712 Date 25 July 05

Signed Janet W. [Signature]