

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

State Well No. 24S/33E-1165E

State Permit No. _____

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

(Do not write above this line)

ref #8

(1) OWNER:

Name Mr. Walter Kliner
Address 1725- 89th. N. E. Bellevue, Wash. 98004

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Driven
Cable Jetted
Dug Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
Irrigation Test Well Other

CASING INSTALLED:

Threaded Welded
10" Diam. from 0 ft. to 600 ft. Gage 2.50
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? Yes No.
Type of perforator used Factory lovered
Size of perforations 1/8 in. by 2 1/2 in.
17,280 perforations from 216 ft. to 600 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? Yes No
Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level.
well to be tested at later date.
Was a pump test made? Yes No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
" " " " " "
" " " " " "
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used cement grout
Well sealed from land surface to 18' ft.
Diameter of well bore to bottom of seal 29" in.
Diameter of well bore below seal 29" in.
Number of sacks of cement used in well seal 7 sacks
Number of sacks of bentonite used in well seal _____ sacks
Brand name of bentonite _____
Number of pounds of bentonite per 100 gallons
of water _____ lbs./100 gals.
Was a drive shoe used? Yes No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? Yes No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? Yes No Size of gravel: 3/8
Gravel placed from 18' ft. to 612' ft.

(10) LOCATION OF WELL:

County Harney Driller's well number _____
S.W. 1/4 n.w. 1/4 Section 16 T.24-s R. 33-e W.M.
Bearing and distance from section or subdivision corner

12' south south west of the center of n.w. 1/4 of sec. 16 - t-24-s/r-33-e

(11) WATER LEVEL: Completed well.

Depth at which water was first found 82' ft.
Static level 11' ft. below land surface. Date 5/14/78
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 29"
Depth drilled 612' ft. Depth of completed well 600' ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
top soil	0	3	
sand--- hard	3	14	
multi colored clays	14	82	
black cinders 3/8 to 1/2"	82	85	
sandy multi colored clays	85	332	
black-blue-gray-green-etc	332		
sandstone&claystone sandy	332	342	
sand&gravel med.	342	349	
claystone&sandy clays	349	497	
gray sandstone	497	505	
gray&green clays	505	523	
fine gray sand	523	527	
5 gray sandstone	527	532	
congl.-limestone claystone	532	571	
gray sandy clay&black sand	571	587	
claystone&sand&sandstone	587	595	
green clay	595	612	

Work started 5/12/78 19 _____ Completed 5/15 19 78

Date well drilling machine moved off of well 5/15/ 19 78

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Burdell J. House Date 6-15-78
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1026

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Water Well Co.
(Person, firm or corporation) (Type or print)

Address 2485 W. MAIN ST. TILLAMOOK, OREG.

[Signed] James R. Price
(Water Well Contractor)

Contractor's License No. 659 Date 6/15/78 19 78