

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

RECEIVED

MAY 23 1966

WATER WELL REPORT

STATE ENGINEER STATE OF OREGON (Please type or print) SALEM, OREGON

G - 3502

State Well No.

24/33-24

State Permit No.

(1) OWNER:

Name RICHARD H. STRAW
Address KAILUA, HAWAII 96734

(2) LOCATION OF WELL:

County Harney Driller's well number
NE 1/4 1/4 Section 24 T. 24S R. 33E W.M.
Bearing and distance from section or subdivision corner

c/o Charles Jacobi, Manager
Box 1042, Yakima, Washington

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
On abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☐
12" Diam. from 0 ft. to 100 ft. Gage 1250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No
Type of perforator used
Size of perforations in. by in.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Well seal—Material used in seal BENTINITE
Depth of seal 30 ft. Was a packer used? NO
Diameter of well bore to bottom of seal 16 to 20 in. MACHINE
Were any loose strata cemented off? ☐ Yes ☒ No Depth N.A.
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel: N.A.
Gravel placed from N.A. ft. to N.A. ft. N.A.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? USABLE Depth of strata N.A.
Method of sealing strata off N.A.

(10) WATER LEVELS:

Static level 10 ft. below land surface Date 5-17-66
Artesian pressure N.A. lbs. per square inch Date _____

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLER
Yield: 500 gal./min. with 9.5 ft. drawdown after 6 hrs.
" " " "

Bailer test N.A. gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow NONE g.p.m. Date _____

Temperature of water COOL Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 12"
Depth drilled 340 ft. Depth of completed well 340 ft.
Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
TOP SOIL & HARDEN STREAKS	0	20
BLUE CLAY WITH SAND	20	60
FINE BLACK SAND	60	97
BLACK LAVA ROCK	97	107
PUMICE STONE	107	130
GREEN CLAY	130	175
PUMICE STONE	175	230
GREEN CLAY	230	240
PUMICE STONE WITH GREEN CLAY STREAKS	240	345
BLACK SANDSTONE	315	330
BLACK CLAY SILT	330	340

(13) PUMP:

Manufacturer's Name WESTERN
Type: TURBINE H.P. 160

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME John W. Rossberg (Person, firm or corporation) (Type or print)

Address Box 443 Burns

Drilling Machine Operator's License No. 269

[Signed] John W. Rossberg (Water Well Contractor)

Contractor's License No. 222 Date 5/1/66, 1966