

RECEIVED
JAN 14 1963

HARN 1054

WATER WELL REPORT

1054
HARN

State Well No. 24/34-6A(1)

File Original and First Copy with the STATE ENGINEER, SALEM, OREGON

STATE ENGINEER
SALEM, OREGON

STATE OF OREGON

State Permit No. G 2528

(1) OWNER: Miller Bros.
Name Miller Bros.
Address Lawen, Oreg

(2) LOCATION OF WELL:
County Harney Owner's number, if any—
1/4 Section 10 T245 R.34E W.M.
Bearing and distance from section or subdivision corner
SW corner of NE 1/4 of NE 1/4 of Sec. 10

(3) TYPE OF WORK (check):
New Well Deepening Reconditioning Abandon
Abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):
Domestic Industrial Municipal Irrigation Test Well Other
(5) TYPE OF WELL:
Rotary Cable Dug Driven Jetted Bored

(6) CASING INSTALLED:
12" Diam. from 0 ft. to 70 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:
Type of perforator used
SIZE of perforations 1/8 in. by 3 in.
perforations from 20 ft. to 69 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:
Well screen installed Yes No
Manufacturer's Name
Type Model No.
Slot size Set from ft. to ft.
Slot size Set from ft. to ft.

(9) CONSTRUCTION:
Was well gravel packed? Yes No Size of gravel: 3/4" minus
Gravel placed from 20 ft. to 69 ft.
Was a surface seal provided? Yes No To what depth? 18 ft.
Material used in seal—Cement
Did any strata contain unusable water? Yes No
Type of water? Depth of strata
Method of sealing strata off

(10) WATER LEVELS:
Static level 19 1/2 ft. below land surface Date 1/1/63
Artesian pressure 2 lbs. per square inch Date

Log Accepted by:
[Signed] Miller Bros. Date 1/1, 1963
by Howard N. Miller (owner)

(11) WELL TESTS:
Drawdown is amount water level is lowered below static level
Was a pump test made? Yes No If yes, by whom? Driller
Yield: 764 gal./min. with 35 ft. drawdown after 20 hrs.
" " " " " "
" " " " " "
" " " " " "
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m. Date
Temperature of water 52 Was a chemical analysis made? Yes No

(12) WELL LOG:
Diameter of well 22 inches.
Depth drilled 70 ft. Depth of completed well 69 ft.
Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
TOP Soil	0	19
FINE SAND	19	22
SAND + CLAY	22	54
COARSE SAND + GRAV.	54	59
YELLOW CLAY	59	70

Work started 12/3 1962 Completed 1/1 1963

(13) PUMP:
Manufacturer's Name Western
Type: Turbine H.P. 50

Well Driller's Statement:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME JOHN W. ROSSBERG
(Person, firm, or corporation) (Type or print)
Address P.O. Box 443
Driller's well number
[Signed] J. Rossberg (Well Driller)
License No. 272 Date 1/1, 1963



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.oregon.gov/owrd

Application for
Well ID Number

RECEIVED

JAN 02 2019

OWRD

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Badger Ventures, LLC
Mailing Address: 68281 Crane-Buchanan Road
City, State, Zip: Burns, OR 97720
Mail Well ID to: [X] SAME AS ABOVE [] In Care Of (C/O)
Name & Address:
City, State, Zip:

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 24 S (North / South) Range: 34 E (East / West) Section: 6 NE 1/4 of the NE 1/4
Tax Lot (usually last 3-5 numbers of Tax Map #): 300 County Harney
GPS Coordinates: Lat: N 43.518858 DD; Long: W -118.574243 DD
Street Address of Well, City: Crane-Buchanan Rd (just under a mile E of)
If the property had a different street address in the past: N/A

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation
Date Well Constructed (or property built): 01-01-1963 Total Well Depth: 70 ft Casing Diameter: 12"
Owner at time the well was constructed (if known): Howard Miller Well Report # (if known): HARN 1054
Other Information: Located in GL 1

SUBMITTED BY (please print): Water Right Services, LLC / John A. Short
PHONE: 541-389-2837 EMAIL &/or FAX: johnshort@usa.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

1-2-19

Well Report Number:

HARN 1054

Well Identification #:

L-133202

HARN 1054

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 43.518858 Datum: WGS84

Longitude: -118.574243

Township/Range/Section/Quarter-Quarter Section:

WM 24S 34E 6 NENE

Address of Well:

CRANE-BUCHANAN RD (E OF)

Well Label: L133202

Well Log: HARN 1054

Printed: January 3, 2019

DISCLAIMER: This map is intended to represent the approximate location of the exempt use well provided by the land owner. It is not intended to be construed as survey accurate in any manner.

Generated by OWRD Staff

