

RECEIVED  
FEB 13 1963

WATER WELL REPORT

STATE ENGINEER STATE OF OREGON

State Well No. 25/31-30 R

State Permit No. HARN

(1) OWNER:

Name EDGAR L. KEENEMAN  
Address Box 296 Burns Oregon

(2) LOCATION OF WELL:

County HARNEY Owner's number, if any—  
SE 1/4 SE 1/4 Section 30 T. 25S R. 31E W.M.  
Bearing and distance from section or subdivision corner

600 FT EAST 40 FT SOUTH  
OF N.W. CORNER,

THIS WELL IS ON MY  
RANCH

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐  
If abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐  
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐  
Cable ☒ Jetted ☐  
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒  
12" Diam. from 0 ft. to 139 ft. Gage STD.  
10" Diam. from 0 ft. to 290 ft. Gage STD.  
" Diam. from " ft. to " ft. Gage "

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

| SIZE of perforations | in. by | in. |
|----------------------|--------|-----|
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Slot size Set from ft. to ft.

Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

Was a surface seal provided? ☐ Yes ☐ No To what depth? ft.

Material used in seal—

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? Depth of strata

Method of sealing strata off

(10) WATER LEVELS:

Static level 81 ft. below land surface Date Jan 10 63

Artesian pressure lbs. per square inch Date

Log Accepted by:

[Signed] Date 19  
(Owner)

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 52 gal./min. with 250 ft. drawdown after 2 hrs.

Artesian flow g.p.m. Date

Temperature of water 54 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well 10" inches.

Depth drilled 660 ft. Depth of completed well 660 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

| MATERIAL               | FROM | TO  |
|------------------------|------|-----|
| TOP SOIL               | 0    | 3   |
| CEMENT GRAVEL          | 3    | 12  |
| YELLOW SAND FINE       | 12   | 88  |
| BLACK SAND FINE        | 88   | 110 |
| BLUE CLAY              | 110  | 256 |
| YELLOW CLAY            | 256  | 377 |
| RED CLAY               | 377  | 415 |
| BLACK CLAY (HARD)      | 415  | 490 |
| GREEN CLAY             | 490  | 573 |
| YELLOW CLAY            | 573  | 618 |
| BLACK CLAY (VERY HARD) | 618  | 660 |

I HAD A LITTLE  
WATER AT 110 FT  
ABOUT 5 GPM. BUT CAGED IT OFF  
AND A LITTLE MORE WATER  
AT 310 FT. ABOUT 2 GPM

I WORKED ON THIS WELL  
OFF AND ON FOR A LONG TIME  
CUT NOW I SHALL THE PIPE  
AND ABANDON THE WELL

Work started APR-7 19 58 Completed JAN 10 19 63

(13) PUMP:

Manufacturer's Name

Type: H.P.

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME EDGAR L. KEENEMAN  
(Person, firm, or corporation) (Type or print)

Address Box 296 Burns Oregon

Driller's well number

[Signed] Edgar L. Keeneman  
(Well Driller)

License No. 428 Date Jan 10, 19 63

323-7-2/62