

WATER WELL REPORT

WATER RESOURCES DEPARTMENT

SALEM, OREGON 97310

within 30 days from the date
of well completion.

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No.

25/33E-10aa

State Permit No.

G 8704

(1) OWNER:

Name Richard O. Adams
Address P.O. Box 854
Crane Ore. 97732

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

12" Diam. from 0 ft. to 113 ft. Gage 4"
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch
Size of perforations 7/8 in. by 8 in.
yes perforations from 60 ft. to 113 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Richard Adams
Flow: 1100 gal./min. with 40 ft. drawdown after 2 hrs.

" " " "
" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement (Concrete)
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 16 in.
Diameter of well bore below seal 12 in.
Number of sacks of cement used in well seal 10 sacks
How was cement grout placed? Wheel barrow

Was a drive shoe used? ☒ Yes ☐ No Plugs Size location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Harney Driller's well number 2
NE 1/4 NE 1/4 Section 10 T. 25S R. 33 E. W.M.

Bearing and distance from section or subdivision corner

600 FT South + 300 FT West of
Section corner (BRASS CAP)

(11) WATER LEVEL: Completed well.

Depth at which water was first found 30 ft.

Static level 23 ft. below land surface. Date 4-10-79

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12"

Depth drilled 280 ft. Depth of completed well 280 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	3'	0
red CLAY	3'	20'	0
Gray CLAY	20	96	23'
Washed gravel 1/2"-3"	96	103	23'
SAND STONE	103	190	23
SAND	190	196	23
Pumice	196	220	23
Hard rock	220	250	23
SAND from course	250	280	23

RECEIVED

FEB 8 1980

WATER RESOURCES DEPT.
SALEM, OREGON

Work started 4-1- 1974 Completed 5-25 1974

Date well drilling machine moved off of well 6-7 1974

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Richard O. Adams Date 7-7 1974
(Drilling Machine Operator)

Drilling Machine Operator's License No. Land

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name (Person, firm or corporation) (Type or print)

Address drilled by Land owner

[Signed] Richard O. Adams
(Water Well Contractor)

Contractor's License No. Date 7-7 1979