

WATER WELL REPORT

STATE OF OREGON

RECEIVED

APR 26 1988

WATER RESOURCES DEPT.
SALEM, OREGON

State Well No.

255/34E-76d

State Permit No.

(1) OWNER:

Name John or Mary McIntosh
 Address P.O. Box 827
 City Crane State ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

☒ Air ☐ Driven ☐
☐ Mud ☐ Dug ☐
☐ Cable ☒ Bored ☐
 Domestic ☒ Industrial ☐ Municipal ☐
 Irrigation ☐ Test Well ☐ Other ☐
 Thermal: ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☐ Plastic ☐
 Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 80 ft. Gauge 250
 " Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
 perforations from ft. to ft.
 perforations from ft. to ft.
 perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal/min. with ft. drawdown after hrs.
 " " " "

Air test gal/min. with drill stem at ft. hrs.

Pump test 30 gal/min. with 10 ft. drawdown after 3 hrs.

Artesian flow g.p.m.

Temperature of water 54.0 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒Well seal—Material used Cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 1 1/4 yards sacks

How was cement grout placed? SlurryWas pump installed? yes Type Sub. HP 1/2 Depth 63 ft.Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Warney Driller's well number
SE 1/4 NW 1/4 Section 7 T. 25 S R. 34 W.M.
 Tax Lot # Lot 3 Blk 28 Subdivision
 Address at well location: CRANE, ORE

(11) WATER LEVEL: Completed well.

Depth at which water was first found 40 ft.
 Static level 30 ft. below land surface. Date 4/8/88
 Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 100 ft. Depth of completed well 95 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil and Clay	0	18	
Sand stone	18	23	
Clay yellow	22	40	40
Clay & sand mixed	40	75	40
Sand stone	75	85	40
Sand coarse	85	100	30

Work started 3/20 19 88 Completed 4/8 1988
 Date well drilling machine moved off of well 4/13 1988

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Robert Rossberg Date 4/13, 1988
 (Drilling Machine Operator)

Drilling Machine Operator's License No. 1336

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Robert Rossberg (Person, firm or corporation)
 (Type or print)

Address

[Signed] Robert Rossberg (Water Well Contractor)

Contractor's License No. 1336 Date 4/20, 1988

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
 SALEM, OREGON 97310
 within 30 days from the date of well completion.

SP-12658-690