

WATER WELL REPORT
STATE OF OREGON

State Well No. 265/30E-16

Harn 1335 *nc*

State Permit No. **HARN 1335**

(1) OWNER:

Name Leo Sullivan
Address 19101 Suncrest Ave.
City West Linn State Ore. 97068

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air Driven
Rotary Mud Dug
 Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
Irrigation Test Well Other
Thermal: Withdrawal Reinjection

(5) CASING INSTALLED:

Steel Plastic
Threaded Welded
14" Diam. from 0 ft. to 120 ft. Gauge .250

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? Yes No

Type of perforator used
Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? Yes No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? Yes No If yes, by whom? Dale Pallin
1200 gal./min. with 40 ft. drawdown after 4 hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 53* Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes No

Well seal—Material used Cement Grout
Well sealed from land surface to 21 ft.
Diameter of well bore to bottom of seal 18 in.
Diameter of well bore below seal 16 in.
Number of sacks of cement used in well seal 45 sacks
How was cement grout placed? Pressure Grouted

Was pump installed? No Type HP Depth ft.

Was a drive shoe used? Yes No Plugs Size: location ft.

Did any strata contain unusable water? Yes No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? Yes No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

N.E. corner of NE 1/4 of NW 1/4
County Harney Driller's well number 2
of S. 1/2 1/4 Section 16 T. 26S R. 30E W.M.
Tax Lot # Lot Blk Subdivision
Address at well location:

(11) WATER LEVEL: Completed well.

Depth at which water was first found 281 ft.
Static level 27 ft. below land surface. Date 5-17-81
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 15"

Depth drilled 330 ft. Depth of completed well 330 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Sand	0	5	
Sandstone	5	35	
Claystone (Green)	35	40	
Black Claystone	40	105	
Lava	105	177	
Lava	177	188	
Brown. Clay Conglom., Water-B.	188	246	
White Cleachy	246	267	
Green Clay	267	281	
Water-Bear. Tan Sandstone	281	300	
Brown Clay	300	320	
	320	330	

RECEIVED

JUN 16 1981

WATER RESOURCES DEPT
SALEM, OREGON

Work started 3-20 19 81 Completed 5-17 1981
Date well drilling machine moved off of well 5-17 19 81

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Dale Pallin Date 6-1, 19.81
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1461

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Orvail Buckner Well Drilling, Inc.
(Person, firm or corporation) (Type or print)

Address 1686 N.E. Negus Way, Redmond, Ore. 97756

[Signed] Orvail Buckner
(Water Well Contractor)

Contractor's License No. 608 Date 6-1, 19 81



Oregon Water Resources Department
 725 Summer Street NE, Suite A
 Salem Oregon 97301
 (503) 986-0900
 www.oregon.gov/owrd

Application for Well ID Number

RECEIVED

SEPT 22 2023

OWRD

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Silver Sage Farms

Mailing Address: 18555 SW Teton Avenue

City, State, Zip: Tualatin, OR 97062

Mail Well ID to: SAME AS ABOVE In Care Of (C/O)

Name & Address: _____

City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 26 S (North / South) Range: 30 E (East / West) Section: 16 NE 1/4 of the SW 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 5000 County Harney

GPS Coordinates: 43.31625904, -119.12917730

Street Address of Well, City: Beyond west end of Weaver Springs Road

If the property had a different street address in the past: _____

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Currently unused (previously irrigation)

Date Well Constructed (or property built): 05/17/1981 Total Well Depth: 330 ft Casing Diameter: 14 inch

Owner at time the well was constructed (if known): Leo Sullivan Well Report # (if known): HARN 1335

Other Information: Well tag # L-95093 installed on well on May 24 2023

SUBMITTED BY (please print): Gerald H. Grondin (OWRD Hydrogeologist)

PHONE: 503-437-5348 EMAIL &/or FAX: Gerald.H.Grondin@water.oregon.gov

To send the completed application, you may MAIL it to: Oregon Water Resources Dept. 725 Summer St NE, Suite A, Salem, Oregon 97301. Or EMAIL the completed PDF form to: Ladeena.K.Ashley@water.oregon.gov, or FAX it to: (503) 986-0902.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

9-22-2023

Well Report Number:

HARN 1335

Well Identification #:

L-95093