

WATER WELL REPORT

STATE OF OREGON

RECEIVED
SEP 10 1985

PLEASE TYPE or PRINT IN INK

State Well No.

State Permit No.

WATER RESOURCES DEPT.

(1) OWNER:

SALEM, OREGON

Name Ralph Killinger
 Address P.O. Box 25
 City Princeton State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐ Domestic ☐ Industrial ☐ Municipal ☐
 Rotary Mud ☐ Dug ☐ Irrigation ☒ Test Well ☐ Other ☐
 Bored ☐ Thermal ☒ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
 Threaded ☐ Welded ☒

12" Diam. from 1 ft. to 84 ft. Gauge 250
 " Diam. from ft. to ft. Gauge

(6) LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Killingerd: 1200 gal./min. with 35 ft. drawdown after 12 hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 56 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒Well seal—Material used CementWell sealed from land surface to 20 ft.Diameter of well bore to bottom of seal 16 in.Diameter of well bore below seal 12 in.Number of sacks of cement used in well seal 20 sacksHow was cement grout placed? Cement Pump +Tr. v. i. pipeWas pump installed? Yes Type Tur. HP 15 Depth 25 ft.Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Harnay Driller's well number 1245
NE 1/4 NE 1/4 Section 1 T. 27S R. 33E W.M.
 Tax Lot # Govt Lot 1 Lot Blk Subdivision
 Address at well location: P.O. Box 25 Princeton

(11) WATER LEVEL: Completed well.

Depth at which water was first found 9 ft.
 Static level 9 ft. below land surface. Date 15 July
 Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12Depth drilled 270 ft. Depth of completed well 270 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	4	
CLAY BROWN	4	40	9
CLAY GRAY	40	70	9
CLAY - SAND	70	75	9
CLAY GRAY	75	105	9
CLAY Blue	105	170	9
CLAY GRAY	170	220	9
CLAY - SAND DARK	220	240	9
CLAY GRAY	240	265	9
CLAY ROCK	265	270	9

Work started 5 Jul 1985 Completed 15 Aug 1985
 Date well drilling machine moved off of well 28 Aug 1985

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Date, 19

Bonded Water Well Constructor Certification:

Bond (number) Issued by: Fidelity Co
 Surety Company Name

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Ralph Killinger
 (Type or print)

Address P.O. Box 25 Princeton, Or 97721

[Signed] Ralph Killinger
 Water Well Constructor

1245 Date 28 Aug, 1985

NOTICE TO WATER WELL CONSTRUCTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,

SALEM, OREGON 97310

within 30 days from the date of well completion.

SP*45292-690