

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

RECEIVED

NOV 20 1962

STATE OF OREGON
SALEM, OREGON

WATER WELL REPORT
(Please type or print)

State Well No. 22/31-36L

G2522

State Permit No.

(1) OWNER:

Name HARRY PON
Address BURNS OREGON

(2) LOCATION OF WELL:

County HARNEY Driller's well number Owner's # 19
SE 1/4 NW 1/4 Section 36 T. 22S R. 31E W.M.
Bearing and distance from section or subdivision corner
LOCATED 500yds NORTH OF HIGHWAY

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐ Rotary ☐ Driven ☐
Irrigation ☒ Test Well ☐ Other ☐ Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(5) TYPE OF WELL:

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
12" Diam. from 1 ft. to 40 ft. Gage 4
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used TORCH
Size of perforations 3/8 in. by 6 in.
200 perforations from 20 ft. to 40 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite Clay
Depth of seal 19 ft. Was a packer used? RECK-SAND
Diameter of well bore to bottom of seal 20 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? Depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 8 ft. below land surface Date 9-20-62
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? PRILLER
Yield: 350 gal./min. with 140 ft. drawdown after 8 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 58 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 11 1/8"
Depth drilled 360 ft. Depth of completed well 360 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
SANDY LOAM SOIL	0	3
CLAY BROWN	3	18
SAND SOME GRAVEL WATER	18	34
CLAY BROWN	34	36
GRAVEL WATER	36	38
CLAY BROWN	38	95
CLAY GREY	95	105
ROCK LAVABLACKY PRWS	105	174
CLAY WHITE	174	185
CLAY BLUE	185	309
CLAY BENTONITE	309	215
CLAY SANDY BLACK	215	224
CLAY BENTONITE	224	234
CLAY SANDY	234	244
CLAY BLUE STICKY	244	293
CLAY BENTONITE	293	308
CLAY GREEN STICKY	308	360

Work started 9-8 1962 Completed 9-20 1962
Date well drilling machine moved off of well 9-20 1962

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Holloway Drilling Co.
(Person, firm or corporation) (Type or print)

Address ONTARIO OREGON

Drilling Machine Operator's License No. 100

[Signed] May Holloway
(Water Well Contractor)

Contractor's License No. 16 Date 11-17, 1962