

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

HARN 1668
WATER WELL REPORT

STATE OF OREGON
(Please type or print)

RECEIVED

OCT 11 1978

State Well No. 335/91E-9ac

Permit No.

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER:

Name CATLO VALLEY FARMS
Address 2650 WASHINGTON BLVD OGDEN UTAH

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

16" Diam. from 41 ft. to 560 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used FACTORY SLOT

Size of perforations 1/8 in. by 3 in.
17,280 perforations from 200 ft. to 560 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom WILSON CO.

Yield: 1350 gal./min. with 170 ft. drawdown after 24 hrs.

" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 54° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT GROUT

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 26 in.

Diameter of well bore below seal 26 in.

Number of sacks of cement used in well seal 28 sacks

How was cement grout placed? TRANSIT MIX - Puddled
to remove any AIR POCKETS OR
BRIDGES ETC.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/8-4

Gravel placed from 20 ft. to 560 ft.

(10) LOCATION OF WELL:

County HARNEY Driller's well number
SW 1/4 NE 1/4 Section 9 T. 33S R. 31E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 94 ft.

Static level 90 ft. below land surface. Date 12-16-77

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 16"

Depth drilled 560 ft. Depth of completed well 560 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	1	
BROWN CLAY & BROWN ROCK	1	185	
BROWN ROCK & FINE GRAVEL	185	202	90'
BROWN CLAY & ROCK	202	335	
BROWN ROCK & GRAVEL	335	352	
BROWN CLAY w/ LOOSE ROCK	352	365	
BROWN CLAY w/ LOOSE BROWN ROCK	365	560	

Work started 12-14 1977 Completed 12-16 1977

Date well drilling machine moved off of well 12-16 1977

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Leoman A. White Date 1-11, 1978
(Drilling Machine Operator)

Drilling Machine Operator's License No. 554

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name HIGHLAND DRILLING CO.
(Person, firm or corporation) (Type or print)

Address P.O. Box 9 LAWEN ORE 97740

[Signed] Leoman A. White
(Water Well Contractor)

Contractor's License No. 577 Date 1-11, 1978



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for Well ID Number

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Jeb Whitby
Mailing Address: 62 W Juniper Rd
City, State, Zip: Mesa, WA 99343
Mail Well ID Tag to: ☒ SAME AS ABOVE ☐ In Care Of (C/O)
Name & Address: _____
City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 33S (North / South) Range: 31E (East / West) Section: 9
Tax Lot: 1100 County HARN SW 1/4 NE 1/4
GPS Coordinates: _____
Street Address of Well, City: 36605 Rock Cr Lane, Frenchglen, OR 97736
If the property had a different street address in the past: _____

III. GENERAL WELL INFORMATION (Please fill out as completely as possible)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation
Date Well Constructed (or property built): 12/16/77 Total Well Depth: 560' Casing Diameter: 16"
Owner at time the well was constructed (if known): Catlow Valley Farms
Other Information: Well log HARN 1668

SUBMITTED BY (please print): Denise A. Montgomery
PHONE: 541-548-5833 EMAIL &/or FAX: neecee@apeands.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

8-14-15

Well Log Number:

HARN 1668

Well Identification #:

L-119813

RECEIVED BY OWRD