

WATER WELL REPORT
STATE OF OREGON

State Well No. 33/34-256(1)
State Permit No. _____

(1) OWNER:

Name Rocky Hill Incorporated
Address 20760 Avenue 314
Exeter, California

(2) LOCATION OF WELL:

County Harney Owner's number, if any—
SW 1/4 NE 1/4 Section 25 T. 33S R. 34E W.M.
Bearing and distance from section or subdivision corner
1410 ft South and 2730 ft East
from Section corner common
to sections 23, 24, 25 & 26

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☒ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☐
12" Diam. from 0 ft. to 420 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used _____

SIZE of perforations	in. by	in.
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.
Was a surface seal provided? ☐ Yes ☒ No To what depth? _____ ft.
Material used in seal—
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ Depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level Flowing ft. below land surface Date 6/17/61
Artesian pressure _____ lbs. per square inch Date _____

Log Accepted by: _____

[Signed] Rocky Hill Inc Date 6/17, 1961
J. J. J. Supr

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLER
Yield: 1000 gal./min. with 90 ft. drawdown after 6 hrs.

" " " "

Bailer test gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow 75 g.p.m. Date 6/17/61

Temperature of water _____ Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well 12 inches.

Depth drilled 509 ft. Depth of completed well 505 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
200'-205' GRAVEL & Sand	200	205
Coarse Sand & fine gravel	205	220
Coarse Sand & Med. Gravel	220	235
Fine Sand	235	260
Gravel Sand	260	288
Fine gravel	288	291
Pure Clay	291	293
Hard Brown Rock	293	297
Fine Sand	297	301
Clay mixture & fine gravel	301	370
Fine Sand	370	373
Medium gravel	373	380
Hard Clay rock	380	387
yellow clay	387	390
Black Rock Rock	390	400
Fine Sand & Gravel	400	404
grey clay	404	416
Large Gravel	416	418
Clay rock	418	420
Clay rock	420	425
Hard Red rock	425	433
Thin Clay rock	433	509

8" bore from 420' to 509'

Work started 5/15/61 19 _____ Completed 6/17/61 19 _____

(13) PUMP:

Manufacturer's Name _____
Type: _____ H.P. _____

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Rosberg & Son
(Person, firm, or corporation) (Type or print)

Address Box 443 Burns, Oreg.

Driller's well number _____

[Signed] John W. Rosberg
(Well Driller)

License No. 272 Date 6/17, 1961

COPY

WATER WELL REPORT
STATE OF OREGON

File Original and
First Copy with the
STATE ENGINEER,
SALEM, OREGON

Willow Creek Well
Application 6-2017
State Well No. *3774-256*

State Permit No. _____

(1) OWNER:

Name Rocky Hill, Incorporated
Address 20700 Avenue 314
Exeter, California

(2) LOCATION OF WELL:

County Harney Owner's number, if any—
SW 1/4 NE 1/4 Section 25 T. 335 R. 34E W.M.
Bearing and distance from section or subdivision corner
1410 Ft. South and 2730 Ft. East from
Section Corner common to Sections 23, 24, 25
& 26

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☐

14 " Diam. from 0 ft. to 200 ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(7) PERFORATIONS:

Perforated? ☐ Yes ☐ No

Type of perforator used Shop - Clean Cut
SIZE of perforations 1/4 in. by 2 in.
_____ perforations from 0 ft. to 200 ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(8) SCREENS:

Well screen installed ☐ Yes ☐ No

Manufacturer's Name _____
Type _____ Model No. _____
_____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.
Was a surface seal provided? ☐ Yes ☒ No To what depth? _____ ft.
Material used in seal—
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ Depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level _____ ft. below land surface Date _____
Artesian pressure _____ lbs. per square inch Date _____

Log Accepted by Rocky Hill
[Signed] Jas. J. J. J. Date 6/21, 1961

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom? _____

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.
" Unsatisfactory " "
" " "

Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow _____ g.p.m. Date _____

Temperature of water _____ Was a chemical analysis made? ☐ Yes ☐ No

(12) WELL LOG:

Diameter of well _____ 14 inches.

Depth drilled 205 ft. Depth of completed well 205 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top Soil	0'	4'
Coarse Dry Gravel	4	21
Water bearing pea gravel	21	24
Water bearing P. Gravel with Clay Stringer	24	60
Packed clay & gravel	60	75
Water bearing pea gravel	75	85
Gray sticky clay & gravel	85	103
Coarse water bearing gravel	103	107
Gravel & clay	107	117
Water bearing gravel	117	118
Gravel & clay	118	138
Water bearing gravel	138	143
Gravel & clay	143	166
Water bearing gravel	166	169
Gravel & sticky clay	169	175
Water bearing gravel	175	180
Brown packed clay & gravel	180'	205'

Work started _____ 19 _____ Completed _____ 19 _____

(13) PUMP:

Manufacturer's Name _____

Type: _____ H.P. _____

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Russell Stooksberry
(Person, firm, or corporation) (Type or print)

Address Winnemucca, Nevada

Driller's well number _____

[Signed] /s/ Russell Stooksberry
(Well Driller)

License No. _____ Date Oct, 1960