

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)
(Do not write above this line)

RECEIVED

MAR 22 1968

State Well No.

34/31-23

STATE ENGINEER

State Permit No.

(1) OWNER:

Name Derrill MorgerAddress 234 Mt. Vernon Ave.
Bakersfield, California

(2) TYPE OF WORK (check):

New Well ☐ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

16" Diam. from 0 ft. to 660 ft. Gage .250

" Diam. from _____ ft. to _____ ft. Gage _____

" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations	in. by	in.
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Water level 54' 8 1/2" ft. below land surface Date 3-1-68

Artesian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static levelpump test made? ☒ Yes ☐ No If yes, by whom? owner600 gal./min. with 120 ft. drawdown after 4 hrs.1500 " 150 " 12 "2200 " 150 " 10 "1700 " 150 " 10 "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date _____

Temperature of water _____ Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Puddled clayDepth of seal 25 ft.Diameter of well bore to bottom of seal 36 in.Were any loose strata cemented off? ☐ Yes ☒ No Depth _____Was a drive shoe used? ☒ Yes ☐ NoDid any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(11) LOCATION OF WELL:

County Harney

Driller's well number _____

1/4 1/4 Section 23 T. 34S R. 31E W.M.

Bearing and distance from section or subdivision corner _____

Located in center of section _____

(12) WELL LOG:

Diameter of well below casing 16"Depth drilled 1000 ft. Depth of completed well 1000 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
brown soil	0	62	
tan clay w/sand & water	62	130	59
brown clay--gritty	130	166	
blue clay--gritty	166	206	
brown clay	206	222	
sticky green clay	222	249	
sticky red clay	249	250	
sticky brown clay	250	254	
grey clay w/fineto med			
sand	254	260	
sticky brown clay w/ occasional streaks sand	260	445	
olive green clay w/ streaks of sandstone	445	470	
green clay	470	540	
various colored clay w/ streaks of sand	540	852	
hard black & grey rock	852	875	54' 8 1/2"
hard, dark grey sandstone	875	990	
hard black rock	990	1000	
Picked up water from 440'. Static level remained same to 852'			

Work started 10-10- 1967 Completed 2-25 1968Date well drilling machine moved off of well 3-6 1968

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Mate-
rials used and information reported above are true to my best
knowledge and belief.

[Signed] Forrest Skinner Date 3-20, 1968
(Drilling Machine Operator)

Drilling Machine Operator's License No. 10

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

NAME Skinner & Sons
(Person, firm or corporation) (Type or print)

Address Crane, Oregon 97732

[Signed] Forrest Skinner
(Water Well Contractor)

Contractor's License No. 312 Date 3-20-68, 1968