

WATER RESOURCES DEPARTMENT.

SALEM, OREGON 97310

within 30 days from the

of well completion.

WATER RESOURCES DEPT.

RECEIVED

STATE OF OREGON

(Please type or print)

WATER RESOURCES DEPT.

SALEM, OREGON

State Well No.

35-133E-26d

State Permit No.

(1) OWNER: SALEM, OREGON

Name Roaring Springs Ranch

Address

French Glenn, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Reverse
Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

16" Diam. from 0 ft. to 400 ft. Gage 250

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used by machine at factory

Size of perforations 16 rows x .125 mesh

perforations from 110 ft. to 400 ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Ballor test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite 35 EPE

Well sealed from land surface to 20' ft.

Diameter of well bore to bottom of seal 20 in.

Diameter of well bore below seal 20 in.

Number of sacks of cement used in well seal sacks

How was cement grout placed?

Was a drive shoe used? ☐ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☐ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☐ No Size of gravel:

Gravel placed from 35 ft. to 484 ft.

(10) LOCATION OF WELL:

County

Driller's well number 3358--2

NW Cor. SE 1/4 Section 26 T. 35 R. 33 W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found ft.

Static level

ft. below land surface. Date

Artesian pressure

lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing

Depth drilled 484 ft. Depth of completed well 400 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
top soil	0	7	
sand and gravel	7	28	
clay	28	68	
sand and gravel	68	134	
clay	134	136	
sand and gravel	136	164	
clay	164	170	
sand and gravel	170	196	
clay	196	210	
sand and gravel	210	245	
clay and sandy clay	245	270	
gravel	270	286	
clay and sandy clay	286	312	
gravel	312	320	
sand and gravel	320	380	
clay and sandy clay	380	390	
gravel	390	400	
clay and sandy clay	400	484	

Work started 19 Completed 5-31-1978

Date well drilling machine moved off of well 5-31-1978

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Date 6-5-1978

(Drilling Machine Operator)

Drilling Machine Operator's License No. 1259 1262

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Eaton Drilling Co. Inc.

Name (Person, firm or corporation) (Type or print)

Address P.O. Box 975 (20 Kentucky)
Woodland, California 95695

[Signed] (Water Well Contractor)

Contractor's License No. 699 Date 6-5 1978