

RECEIVED

HOBBSMATION WELL

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON (Please type or print)

Handwritten: 1806, 6-4409, 6-4410

State Well No. 39/35-25 State Permit No.

(1) OWNER: FRANK +

Name DON ORLANDO Trout Creek Ranch Address ANDREWS OREGON

(2) LOCATION OF WELL:

County HARNEY Driller's well number SW 1/4 NE 1/4 Section 25 T. 39S R. 35E W.M. Bearing and distance from section or subdivision corner IN NE Corner of SW 1/4 of NE 1/4 of sec 25

(3) TYPE OF WORK (check):

New Well [X] Deepening [] Reconditioning [] Abandon []

(4) PROPOSED USE (check):

Domestic [] Industrial [] Municipal [] Irrigation [X] Test Well [] Other []

(5) TYPE OF WELL:

Rotary [X] Driven [] Cable [] Jetted [] Dug [] Bored []

(6) CASING INSTALLED:

Threaded [] Welded [X] 1 1/2" Diam. from 0 ft. to 400 ft. Gage 1/4"

(7) PERFORATIONS:

Perforated? [X] Yes [] No Type of perforator used MILL CUT Size of perforations 3/16 in. by 3 in. 9280 perforations from 100 ft. to 290 ft.

(8) SCREENS:

Well screen installed? [] Yes [X] No Manufacturer's Name Type Model No. Slot size Set from ft. to Diam. Slot size Set from ft. to

(9) CONSTRUCTION:

Well seal—Material used in seal PUDDLED BENTONITE Depth of seal 20 ft. Was a packer used? NO Diameter of well bore to bottom of seal 30 in. Were any loose strata cemented off? [] Yes [X] No Depth Was a drive shoe used? [] Yes [X] No Was well gravel packed? [X] Yes [] No Size of gravel: 3/4 MINUS Gravel placed from 0 ft. to 400 ft. Did any strata contain unusable water? [] Yes [X] No Type of water? depth of strata Method of sealing strata off

(10) WATER LEVELS:

Static level 10 ft. below land surface Date 6-14-66 Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level Was a pump test made? [X] Yes [] No If yes, by whom? MCGUIRE DRILLING Yield: 2000 gal./min. with 90 ft. drawdown after 24 hrs. Baller test NONE gal./min. with ft. drawdown after hrs. Artesian flow NONE g.p.m. Date Temperature of water COLD Was a chemical analysis made? [] Yes [X] No

(12) WELL LOG:

Diameter of well below casing Depth drilled 400 ft. Depth of completed well 400 ft. Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

Table with columns MATERIAL, FROM, TO. Rows include TOP SOIL, GRAVEL MED, CLAY B, GRAVEL MED, CLAY B, GRAVEL MED, CLAY B, GRAVEL MED, CLAY B, SAND & GRAVEL, CLAY B, GRAVEL MED, CLAY B, GRAVEL MED, CLAY B, GRAVEL, CLAY B.

3/8" X 30" X 20' Conductor casing installed at top 20' sealed with Bentonite Work started MAY 25 1966. Completed JUNE 14 1966 Date well drilling machine moved off of well JUNE 15 1966

(13) PUMP:

Manufacturer's Name JACUZZI Type TURBINE H.P. 75

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME MCGUIRE DRILLING Co (Person, firm or corporation) Address P.O. BOX 1516 PAYETTE IDA Drilling Machine Operator's License No. 81 [Signed] J. L. McGuire (Water Well Contractor) Contractor's License No. 382 Date June 14, 1966

HARN 1806

For Official Use Only by The Oregon Water Resources Department:

Received Date:

County Well Log ID #

Well Identification Tag #

Harn 1806

L94722

APPLICATION FOR WELL IDENTIFICATION TAG

LANDOWNER INFORMATION

Name: Stafford Ranches

Mailing Address: 4411 NW Elliott Lane

City: Prineville

State: OR

Zip: 97754

Return Well Tag to (if different than mailing address): _____

WELL LOCATION INFORMATION

County: Harney Township: 39 North or South (circle one) Range: 35 East or West (circle

Section: 25 NW 1/4 SE 1/4 Tax Lot #: _____

Street Address of Well (if different than mailing address): Whitchorse Ranch Road

(south Harney county)

WELL INFORMATION (Do Not Complete If Well Report is Attached)

Type of Well (i.e. domestic, irrigation, etc): Irrigation Date Well Constructed: 6-14-66

Well Constructor/Company: McGuire Drilling Co.

Well Depth (in feet): 400 Diameter of Well Casing (in inches): 16

Landowner Who Had Well Constructed or Previous Owner at the Time Well was Constructed (if known):

Frank & Don Orlando

Other Information: _____

TAGGED BY JR JOHNSON, DIST 10

Return to: Oregon Water Resources Department, ~~Janet Holladay~~, 725 Summer St. NE, Suite A, Salem, OR 97301-1271, (503) 986-0854 or fax to 503-986-0902

App for tag