

MAY 16 1997

WATER RESOURCES DEPT.

(START CARD) # 83818

Instructions for completing this report are on the last page of this form.

(9) LOCATION OF WELL by legal description:

County Harney Latitude _____ Longitude _____
Township 24S N or S Range 30E E or W. WM. _____
Section 7 SW 1/4 NW 1/4
Tax Lot 800 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Hwy 20 W
Sage Hen Valley

(10) STATIC WATER LEVEL:

23.5 ft. below land surface. Date 5-5-97
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 43

From	To	Estimated Flow Rate	SWI
45	400	1000	15.3

(12) WELL LOG:

Ground Elevation

Material	From	To	SWL
Clay topsoil	0	1	
Clay gravel fine	1	10	
Clay gravel	10	35	
Clay	35	43	
Sand/pumice/obsidian	43	85	23.5
Sandstone soft	85	102	
Sandstone hard	102	129	
Pumice/sand med	129	160	
Gravel/pumice sand	160	164	
Rock brn	164	173	
Pumice brn	173	177	
Rock	177	186	
Gravel clay	186	192	
Pumice/obsidian	192	219	
Rock red broken	219	222	
Sandstone brn	322	365	
Rock red broken	365	375	
Sandstone brn	375	380	
Rock clay broken	380	400	23.5

Date started 4-16-97 Completed 5-5-97

(unbonded) Water Well Constructor Certification:

I certify that the work performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed

Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1424

Signed

Date 5-5-92

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☒ Bailer ☐ Air ☐ Flowing
Yield gal/min Drawdown Drill stem at Time

140	10		1 hr.

Temperature of water 58 Depth Artesian Flow Found

Was a water analysis done? no ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER