

harn 50368

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Well Number _____

Name Tony Lasich

Address LS Ranch

City Burns

State Ore

Zip 97720

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 140 ft.

Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
18"	0	48	Bentonite	0	48	49
14"	48	140	_____	_____	_____	_____
12"	140	165	Gravel	140	165	2 yds

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other air inject

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 14"	+2	75	12.8	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☐ Perforations

☐ Screens

Method

Type

Material

From	To	Slot size	Number	Diameter	Tube/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump

☐ Bailor

☒ Air

☐ Flowing

☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
1000+	1.35	162	1 hr.
1000+	5.3	25	4.5

Temperature of water 56 Depth Artesian Flow Found 61

Was a water analysis done? No ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other NO

Depth of strata: _____

WELL I.D.# 211268

(START CARD) # 116925

(9) LOCATION OF WELL by legal description:

County Harney Latitude _____ Longitude _____

Township 25 S N or S Range 31 E E or W. WM.

Section 21 SW 1/4 SE 1/4

Tax Lot 4000A Block _____ Subdivision _____

Street Address of Well (or nearest address) LS Ranch

(10) STATIC WATER LEVEL:

32 ft. below land surface.

Date 5-10-98

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 61

From	To	Estimated Flow Rate	SWL
61	94	1000+	32
103	158	1000+	32

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Top Soil	0	12	-
Brown Fractured Shale	12	26	-
Brown + Grey Sand	26	41	-
Blue Clay	41	61	-
Brown Sandstone			-
w/Vascular Brown			-
Shale (w/S)	61	94	32
Blue Clay	94	103	-
Brown Sand Stone	103	158	32
Blue Clay	158	165	

RECEIVED

NOV 30 1998

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 5-5-98 Completed 5-10-98

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____

Signed _____

Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1521

Signed Daniel H. Kend

Date 10-25-98

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER