

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

WELL I.D. # 32863
START CARD # 120922

(1) OWNER: Well Number _____

Name Ed Chotard
Address 9227 North West Boise Drive
City Madras State OR Zip 97741

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 78 ft.

Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
18"	0	28'	Pentonite	0	28'	34
12"	28'	78'	Cement	23'	28'	7

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Cement with dump bailer

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 12"	+1'	76'	29	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s) 76'

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Hand Torch
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
36'	76'	3/32"	590	12"		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing
Yield gal/min Drawdown Drill stem at Time
700 34' 24 hr

Temperature of water 55 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Harney Latitude _____ Longitude _____
Township 23 N or S Range 34 E or W. WM.
Section 30 SW 1/4 NE 1/4
Tax Lot 1500 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 900 Buchanan Rd.

(10) STATIC WATER LEVEL:

18' ft. below land surface. Date 10-2-99
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 30'

From	To	Estimated Flow Rate	SWL
30'	32'	40 GPM	18'
41'	78'	700 GPM	18'

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Top Soil Sandy Loam	0	2'	
Sand Stone	2'	6'	
Brown Clay	6'	41'	18'
Brown Sand-Coarse	41'	78'	

RECEIVED

OCT 25 1999

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 8-20-99 Completed 10-2-99

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed George Valentine WWC Number 1675
Date 10-4-99

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Joe Valentine WWC Number 1435
Date 10-4-99