

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

HARN
50684

WELL I.D. # 137258-134015
START CARD # 127204

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Well Number _____

Name Norm Bundgard
Address HC 77 Box 86
City Princeton State OR Zip 97721

(2) TYPE OF WORK Replacement

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☐ No Depth of Completed Well 200 ft.

Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
15"	0	200	Neat cement	0	30	21 Sacks

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☐ Other Trimmed

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from 30 ft. to 200 ft. Size of gravel 1/8 x 1/4

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	10 3/4"	+1	200	1/4"	☒	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Saw Cut

☐ Screens Type Mill Slot Material Steel

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
40	200	.100	DR	10 3/4"		☒	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump	☐ Bailer	☒ Air	☐ Flowing
Yield gal/min	Drawdown	Drill stem at	Time
600		200	1 hr.

Temperature of water 76° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Harney Latitude _____ Longitude _____
Township 37 S N or S Range 33 E E or W. WM.
Section 9 NW 1/4 NE 1/4
Tax Lot 300 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 27517 Alvord Rd.
Fields, OR 97721

(10) STATIC WATER LEVEL:

20' ft. below land surface. Date 5/29/01
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 35

From	To	Estimated Flow Rate	SWL
35	200	600	20

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Clay	0	15	
Sand & clay	15	23	
Clay w/pea gravel	23	25	
Clay	25	35	
Volcanic sand	35	50	
Volcanic sand & brown clay	50	60	
Clay w/sand layers	60	170	
Sand & pea gravel	170	180	
Clay & sand layers	180	200	

RECEIVED

RECEIVED

JUN 18 2001

AUG 02 2001

WATER RESOURCES DEPT.
SALEM, OREGON

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 5/28/01 Completed 5/29/01

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____

Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1598

Signed R. J. [Signature] Date _____



Oregon Water Resources Department
 725 Summer Street NE, Suite A
 Salem Oregon 97301
 (503) 986-0900
 www.oregon.gov/owrd

Application for Well ID Number

RECEIVED

APR 24 2019

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Waldron Farms, LLC

OWRD

Mailing Address: 20680 Miami Foley Rd.

City, State, Zip: Bay City, OR 97107

Mail Well ID to: ☒ SAME AS ABOVE ☐ In Care Of (C/O)

Name & Address: _____

City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 37S (North / South) Range: 33E (East / West) Section: 9 SW 1/4 of the NE 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 400 County Harney

GPS Coordinates: 42.345802 deg N & 118.634734 deg W

Street Address of Well, City: 27517 East Steens Rd. Princeton, OR 97721-9549

If the property had a different street address in the past: 27517 Alvord Rd. Fields, OR 97721

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation

Date Well Constructed (or property built): 5-29-2001 Total Well Depth: 200 ft. Casing Diameter: 10.75"

Owner at time the well was constructed (if known): Norm Bundgard Well Report # (if known): HARN 50684

Other Information: Tag L 37258 has been lost and WE need a new tag.

SUBMITTED BY (please print): Amber Waldron

PHONE: (503)322-2278

EMAIL &/or FAX: waldronland@gmail.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
 Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

4-24-19

Well Report Number:

HARN 50684

Well Identification #:

L-134015