

STATE OF OREGON

WATER SUPPLY WELL REPORT

(as required by ORS 537.765 & OAR 690-205-0210)

WELL LABEL # L 93559START CARD # 197392

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER

Owner Well I.D.

First Name VONNE Last Name LEACHCompany 4153 NE COLLINS DRCity MADRAS State OR Zip 97741(2) TYPE OF WORK ☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD

☒ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☐ Domestic ☒ Irrigation ☐ Community☐ Industrial/Commercial ☐ Livestock ☐ Dewatering ☐ Injection☐ Thermal ☐ Other(5) BORE HOLE CONSTRUCTION Special Standard: ☐ Yes (attach copy)Depth of Completed Well 252 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amount	Scks/lbs
24"	0	30	BENT	0	30	65	Scks
20"	30	55					
16"	55	268					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other POURED DRYBackfill placed from 0 ft. to 128 ft. Material PER GRAMSFilter pack from 0 ft. to 128 ft. Material PER GRAMS Size 3/8Explosives used: ☐ Yes Type Amount

(6) CASING/LINER

Csng	Linr	Dia	+	From	To	Gauge	Steel	Plastic	Welded	Thrd
✓		20"	+	1 1/2'	38 1/2'	250	✓		✓	
	✓	14"	+	2'	228	250	✓		✓	

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s)Temporary casing ☐ Yes Diameter From To

(7) PERFORATIONS/SCREENS

Perforations Method SAUND

Screens Type Material

Perf	Scrn	Csng	Linr	Screen Dia	From	To	Screen/ slot width	Slot length	# of slots	Tele/ pipe size
✓			✓		-188	228	1/8	3"	1120	PIPE

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)

520 220' 3 hr.Temperature 53 °F Lab analysis ☐ Yes ☒ NoWater quality concerns? ☐ Yes (describe below)

From To Description Units

JUL 25 2008

WATER RESOURCES DEPT.

SALEM, OREGON

(9) LOCATION OF WELL (legal description)

County HARNEY Twp 23 N or S Range 33 E or W W.M.Sec 29 SE 1/4 of the SE 1/4 Tax Lot 600

Tax Map Number Lot

Lat " or DMS or DD

Long " or DMS or DD

Street Address of Well (or nearest address) PENNY RD

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well/Predeepening				
Completed Well	<u>7-20-08</u>			<u>35</u>

Flowing Artesian? ☐ Yes Dry Hole? ☐ Yes

WATER BEARING ZONES Depth water was first found

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
<u>5-21-08</u>	<u>17</u>	<u>19</u>	<u>5</u>			<u>1272</u>
<u>7-20-08</u>	<u>42</u>	<u>268</u>	<u>600+</u>			<u>35</u>

(11) WELL LOG

Ground Elevation 4150

Material	From	To
SANDY TOP SOIL	0	3
BROWN CLAY	3	17
FINE BRN SAND	17	19
GRAY CLAY	19	42
FRACT. GRAY CLAY	42	46
GRAY CLAY - SAND STREAKS	46	205
BROKEN GRAY CLAYSTONE	205	238
VOLCANIC MATEIX - ROCK	238	268
GRAVEL - PUMICE		268
Bottom 16' Loose material filled in @ 252'		

Date Started 5-21-08 Completed 7-20-08

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1739 DateSigned Charles Viny

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1355 Date 7-24-08Signed Ruth & Jay

Contact Info. (optional)