

RECEIVED

MAY 15 2009

HARN 51574

WATER RESOURCE DEPT. EASTERN REGION

STATE OF OREGON WATER SUPPLY WELL REPORT (as required by ORS 537.765)

(START CARD) # 63155

Instructions for completing this report are on the last page of this form.

(1) OWNER: RIM Well Number

Name RIM Address HC 74-12533 HWY 20 WEST City LLINAS State OR Zip 97738

(2) TYPE OF WORK: [X] New Well [] Deepening [] Alteration (repair/recondition) [] Abandonment

(3) DRILL METHOD: [X] Rotary Air [] Rotary Mud [] Cable [] Auger [] Other

(4) PROPOSED USE: [] Domestic [] Community [] Industrial [] Irrigation [] Thermal [] Injection [] Livestock [X] Other CAMPGROUND LAND PARD

(5) BORE HOLE CONSTRUCTION: Special Construction approval [] Yes [X] No Depth of Completed Well 220 ft.

Explosives used [] Yes [X] No Type Amount

HOLE SEAL Diameter From To Material From To Sacks or pounds

17 0 20 BENTONITE 0 20 18 SCKS

8 20 220

How was seal placed: Method [] A [] B [] C [] D [] E [X] Other DRY GRANULAR BENTONITE

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Diameter From To Gauge Steel Plastic Welded Threaded

Casing 8 0 220 240 [X] [] [X] [] [] []

Final location of shoe(s)

(7) PERFORATIONS/SCREENS: [X] Perforations Method SAWN SLOTS [] Screens Type Material

From To Slot size Number Diameter Telephone size Casing L.ner

160 220 1/8 912 8 PIPE [X] [] [] []

(8) WELL TESTS: Minimum testing time is 1 hour

[X] Pump [] Bailor [] Air [] Flowing Artesian

Yield gal/min Drawdown Drill stem at Time

1.8 31 3 hrs

Temperature of water 57 ° Depth Artesian Flow Found

Was a water analysis done? [] Yes By whom

Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County HARNEY Latitude Longitude

Township 34 S N or S Range 32 3/4 E or W. WM.

Section 4 SE 1/4 NW 1/4

Tax Lot Lot Block Subdivision

Street Address of Well (or nearest address)

SOUTH STEENS CAMP GROUND

(10) STATIC WATER LEVEL: 109 ft. below land surface. Date 7-10-95

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 178

Table with columns: From, To, Estimated Flow Rate, SWL

178 220 2 GPM 109

(12) WELL LOG:

Ground Elevation

Table with columns: Material, From, To, SWL

CLAY HARD YELLOW 0 8

BRKN BASALT/BROWN CLAY 8 38

CLAY RED 38 47

ROCK SOFT BROWN VOLC 47 66

BRKN BASALT/BROWN CLAY 66 75

CINDER RED 75 83

ROCK SOFT BROWN VOLCANIC 83 97

CINDER RED 97 106

CINDER GRAY 106 108

CINDER RED 108 123

ROCK BROWN VOLCANIC 123 185 109

BLACK ROCK/PINK CLAY 185 220 "

Date stoned 7-5-95 Completed 7-10-95

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards.

Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 773

Signed Date 7-26-95

ORIGINAL & FIRST COPY WATER RESOURCES DEPARTMENT SECOND COPY CONSTRUCTOR THIRD COPY CUSTOMER

RECEIVED

MAY 29 2009

WATER RESOURCES DEPT SALEM, OREGON

118° 43' 41.81" W
42° 39' 20.55" N



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

RECEIVED

AUG 07 2017

Do not complete if the well already has a Well Identification Number.

WATER RESOURCES DEPT
SALEM, OREGON

I. OWNER INFORMATION

Current Owner Name (please print): US Bureau of Land Management
Mailing Address: 28910 US-20
City, State, Zip: Hines, OR 97738
Mail Well ID Tag to: [] SAME AS ABOVE [] In Care Of (C/O)
Name & Address:
City, State, Zip:

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 34S (North / South) Range: 32.75E (East / West) Section: 4
Tax Lot: 200 County Harney SE 1/4 NW 1/4
GPS Coordinates: 42.65577, -118.72824
Street Address of Well, City:
If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Please fill out as completely as possible)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Campground
Date Well Constructed (or property built): 7/10/1995 Total Well Depth: 220 Casing Diameter: 6
Owner at time the well was constructed (if known): US BLM
Other Information:

SUBMITTED BY (please print): Darrick E. Boschmann
PHONE: 503-986-0853 EMAIL &/or FAX: darrick.e.boschmann@oregon.gov

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

8-7-17

Well Log Number:

HARN 51574

Well Identification #:

L-95070