

**STATE OF OREGON
WATER SUPPLY WELL REPORT**

HARN 53296

WELL I.D. LABEL# L

156871

START CARD #

1082564

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/7/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name LOUIELast Name MOLT

Company _____

Address 72299 TURN OUT RDCity BURNSState ORZip 97720**(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal:

(3) DRILL METHOD
☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other _____
(4) PROPOSED USE☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____
(5) BORE HOLE CONSTRUCTIONSpecial Standard ☐ (Attach copy)Depth of Completed Well 245.00 ft.

BORE HOLE				SEAL				sacks/
Dia	From	To	Material	From	To	Amt		lbs
12	0	245	Bentonite Chips	0	39	33	S	
					Calculated	31.36		
					Calculated			

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POURED&TAGGED

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from 39 ft. to 245 ft. Material SAND Size 8/12Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 7/22/2026 Begin Time 12 00**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount _____

Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Shoe Location
C	6	☒	2	245	0.250	ST	☒			

Temp casing ☐ Yes Dia _____ From + ☐ _____ To _____**(7) PERFORATIONS/SCREENS**

Perforations Method _____

Screens Type WIRE WRAP Material SS

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Casing	6	75	117	.025			Pipe Size
Screen	Casing	6	137	169	.025			Pipe Size
Screen	Casing	6	210	220	.025			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	100		245	1.5

Temperature 53 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 210 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County HARNEY Twp 23.00 S N/S Range 32.00 E E/W WMSec 19 SE 1/4 of the SW 1/4 Tax Lot 200

Tax Map Number _____ Lot _____

Lat _____ ° _____ ' _____ " or 43.55552672 DMS or DD

Long _____ ° _____ ' _____ " or -118.93202892 DMS or DD

☒ Street address of well ☐ Nearest address33710 RYE GRASS LANE BURNS OR 97720**(10) STATIC WATER LEVEL**

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/23/2026			46
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 46.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
7/23/2026	46	245	100			46

(11) WELL LOGGround Elevation 4138.80 FT

Material	From	To
BLACK CLAY	0	6
COARSE SAND/GRAVEL	6	18
BLACK SAND W/CLAY	18	26
GREY CLAY	26	40
BLACK SANDSTONE	40	42
GREY CLAY	42	45
COARSE SAND/GRAVEL	45	130
FINE SAND W/GREY CLAY	130	168
GREY CLAY	168	210
BROKEN CLAYSTONE W/ GRAVEL	210	220
HARD GREY CLAY	220	239
GREEN SANDY CLAY	239	245

Construction

Begin Date 7/17/2026 Begin Time 12 50 End Date 7/23/2026**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2128 Date 7/27/2026Signed CYRUS WEDEL (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 2094 Date 7/27/2026Signed JAY NELSON (E-filed)Drilling Company: SURETAP SPRINGS LLC

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

HARN 53296

8/7/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 43.55552672 Datum: WGS84

Longitude: -118.93202892

Township/Range/Section/Quarter-Quarter Section:
WM23.00S32.00E19SESW

Address of Well:

33710 RYE GRASS LANE BURNS OR 97720

Well Label: 156871

Printed: July 27, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

