

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON (Please type or print)

State Well No. 23/32-11D

State Permit No.

(1) OWNER:

Name Joseph H. Rouse
Address 471 W. Harney
Glendale 4 Calif.

AUG 11 1964

(2) LOCATION OF WELL:

County Harney Driller's well number
1/4 1/4 Section 11 T. 23S R. 32E W.M.

Bearing and distance from section or subdivision corner

12 E of Barn 1 mi S of Hwy 20

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
24" Diam. from 0 ft. to 30 ft. Gage 250
12" Diam. from 0 ft. to 106 ft. Gage 250
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used machine
Size of perforations 3/16 in. by 3 in.
perforations from 47'6" ft. to 90 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☒ Yes ☐ No
Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Clay
Depth of seal 30 ft. Was a packer used? no
Diameter of well bore to bottom of seal in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3" to 3"
Gravel placed from 0 ft. to 90 ft. 8 4
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? Depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 9 ft. below land surface Date 8/6/64
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller
Yield: 580 gal./min. with 29 ft. drawdown after 30 hrs.
" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 64 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 0
Depth drilled 90 ft. Depth of completed well 90 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
TOP SOIL	0	3
fine sand	3	18
blue clay	18	60
fine sand	50	60
blue clay	60	85
fine sand	85	89
course gravel	89	90
blue clay	90	106
drilled to 90' casing driven to 106' and blue clay plug left in tubing below 90'		

Work started 5/20 19 64 Completed 8/6 19 64
Date well drilling machine moved off of well 8/10 19 64

(13) PUMP:

Manufacturer's Name Western
Type: turbine H.P. 15

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME John W. Rossberg (Person, firm or corporation) (Type or print)

Address Box 443 Burns Oreg.

Drilling Machine Operator's License No. 269

[Signed] John W. Rossberg (Water Well Contractor)

Contractor's License No. 222 Date 8/6 19 64