

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

State Well No. 23/32-1366
State Permit No. _____

(1) OWNER:

Name Elton E. Sneed
Address 642 Girard St San Francisco Cal

(2) LOCATION OF WELL:

County HARNEY Driller's well number
NW 1/4 1/4 Section 13 T. 23S R. 32E W.M.
Bearing and distance from section or subdivision corner
50 ft east 200 ft south of NW1/4
North west corner of the NW1/4
of sec. 13

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
14" Diam. from 0 ft. to 232 ft. Gage 1/4 in
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Mill Cut
Size of perforations 3/16 in. by 3 in.
8000 perforations from 72 ft. to 240 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☒ Yes ☐ No

Manufacturer's Name _____ Model No. _____
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal cement
Depth of seal 18 ft. Was a packer used? no
Diameter of well bore to bottom of seal 24 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/4 minus
Gravel placed from 18 ft. to 232 ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ Depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level 13 ft. below land surface Date 10/22/63
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 100 gal./min. with no ft. drawdown after 3 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☐ No

(12) WELL LOG:

Diameter of well below casing _____

Depth drilled 232 ft. Depth of completed well 232 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top soil	0	8
Br Clay	8	46
Blue Clay	46	66
Gravel Course	66	72
Clay Blue	72	103
Gravel Course	103	111
Clay Blue	111	158
Gravel Med	158	163
Clay Blue	163	188
Gravel Med	188	195
Clay Blue	195	203
Gravel Course	203	230
Hard Rock	230	232

This well is 24 in with 14 in casing
gravel packed with a cement seal at
18 ft with a 6 in. X 1/4 in. gravel
chute

Will be tested this week by
Eastern Oregon Mills Of Bend, Ore.

Work started Oct 15 1963 Completed Oct 21 1963

Date well drilling machine moved off of well Oct 23 1963

(13) PUMP:

Manufacturer's Name _____
Type: _____ H.P. _____

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME McGuire Drilling Co.
(Person, firm or corporation) (Type or print)

Address Box 909 Burns, Oregon

Drilling Machine Operator's License No. 81

[Signed] J. C. McGuire
(Water Well Contractor)

Contractor's License No. 383 Date Oct 23, 1963.