

RECEIVED

G 4985

JUL 9 1968

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER
SALEM OREGON

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date of well completion.

STATE OF OREGON
(Please type or print)

State Well No. 23/32 1/2 - 1 #
State Permit No. G-4703

(1) OWNER:

Name E. A. McConville
Address Buchanan Pt. Burns, Oreg.

(2) LOCATION OF WELL:

County Harnes Driller's well number
SE 1/4 NE 1/4 Section 1 T. 23 S. R. 32 E W.M.
Bearing and distance from section or subdivision corner
1/2 mi S + 1/4 mi E of main porch building

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐ Rotary ☐ Driven ☐
Irrigation ☒ Test Well ☐ Other ☐ Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
12" Diam. from 0 ft. to 11.5 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used TORCH
Size of perforations 7/16 in. by 5 in.
perforations from 20 ft. to 100 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☒ Yes ☐ No
Manufacturer's Name
Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Concrete
Depth of seal 20 ft. Was a packer used? yes
Diameter of well bore to bottom of seal 24 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☐ No Size of gravel: 3/4 to 3/8
Gravel placed from 20 ft. to 105 ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 12 ft. below land surface Date 4/12/68
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water cool Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 0
Depth drilled 115 ft. Depth of completed well 105 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
TOP SOIL + HARD PAN	0	15
BLUE CLAY	15	40
BROWN CLAY + GRAVEL	40	65
BLUE CLAY	65	90
FINE BLACK SAND	90	110
CLAY (HARD)	110	115

500 S.P.M. pump installed
well appears to have approx
1000 S.P.M. no pump test
was made at top of
completion of well at 500 S.P.M.
at this time.

Work started 3-2-1968 Completed 4-12-1968
Date well drilling machine moved off of well 4-12-1968

(13) PUMP:

Manufacturer's Name Western Pump
Type: Turbine H.P. 15

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME JOHN W. ROSSBERG
(Person, firm or corporation) (Type or print)
Address P.O. Box 638 CLATSOP OREG.

Drilling Machine Operator's License No. 269

[Signed] John W. Rossberg
(Water Well Contractor)

Contractor's License No. 222 Date 4-20-1968