

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

WATER WELL REPORT NOV 19 1969

STATE OF OREGON STATE ENGINEER

(Please type or print) SALEM, OREGON

(Do not write above this line) State Permit No.

6-5216

6-5213

23/33-8a

(1) OWNER:

Name W. P. Hankins
Address Buchanan Pt. Burns, Oreg

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☐
12" Diam. from 0 ft. to 120 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used Torch
Size of perforations 1/8 in. by 8 in.
1080 perforations from 30 ft. to 110 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 8 ft. below land surface Date 10-28-69
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Rossberg
Yield: 1250 gal./min. with 47 ft. drawdown after 120 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 60 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Bentonite
Depth of seal 20 ft.
Diameter of well bore to bottom of seal 20 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/8 to 3/4

Gravel placed from 20 ft. to 110 ft.

(11) LOCATION OF WELL:

County Harney Driller's well number
1/4 NE 1/4 Section 8 T. 238 R. 33E W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 12"

Depth drilled 365 ft. Depth of completed well 110 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top Soil	0	10	
Clay & sand	10	20	
Clay	20	37	
medium gravel	37	42	
Clay - sand & gravel	42	63	
sand with sea shells	63	110	
Clay Blue	110	120	
hard stone	140	145	
Green & blue clay	145	365	

This well was drilled on my own land, with my own machine with my own labor.

Work started 10-20 1969 Completed 10-28 1969

Date well drilling machine moved off of well 10-30 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Jesse Hankins Date 10-28, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME (Person, firm or corporation) (Type or print)

Address

[Signed] (Water Well Contractor)

Contractor's License No. Date 19