

ORIGINAL
File Original, and
Duplicate with the
STATE ENGINEER,
SALEM, OREGON

WATER WELL DRILLERS REPORT

STATE OF OREGON

G197

Do Not
Fill In

State Well No. _____

State Permit No. _____

24/30-2461

(1) OWNER:

Name W.F. ClaytonAddress P.O. Box 8
Burns, Oregon

(2) LOCATION OF WELL:

County Hailey Owner's number, if any— #1R. F. D. or Street No. Box 8 Burns, Ore

Bearing and distance from section or subdivision corner _____

(3) TYPE OF WORK (check):

New well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) EQUIPMENT:

Rotary ☐
Cable ☒
Dug Well ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

FROM 0 ft. to 930 ft. Diam. 3/16 Gage or Wall 18

" " " " " "
" " " " " "
" " " " " "

If gravel packed

Diameter of Bore	from ft.	to ft.

Type and size of shoe or well ring 18-6-3/4 Size of gravel: _____Describe joint welded

(7) PERFORATIONS:

Type of perforator used 1/4" X 3 1/2" SLOTS

SIZE of perforations	in., length, by	in.
FROM ft. to ft.	per foot	No. of rows
" " " "	" " "	" " "
" " " "	" " "	" " "
" " " "	" " "	" " "
" " " "	" " "	" " "

SCREENS:

Give Manufacturer's Name, Model No. and Size _____

(8) CONSTRUCTION:

Was a surface sanitary seal provided? ☒ Yes ☐ No To what depth 30 ft.Were any strata sealed against pollution? ☒ Yes ☐ No
If yes, note depth of strata _____FROM 60 ft. to 71 ft.METHOD OF SEALING dove casing into clay

(9) WATER LEVELS:

Depth at which water was first found Artesian ft.

Standing level before perforating _____ ft.

Standing level after perforating _____ ft.

Log Accepted by: _____

[Signed] _____ Dated _____, 19____
Owner _____

(10) WELL TESTS:

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Inter-#4 ST. PUMP Co.Yield: 2200 gal./min. with 85 ft. draw down after 4 hrs.

" " " "

Artesian flow 250 g.p.m.Shut-in pressure Unknown lbs. per square inch.Boiler test none g.p.m. with _____ ft. drawdownTemperature of water 58 Was a chemical analysis made? ☐ Yes ☒ NoWas electric log made of well? ☐ Yes ☒ No

(11) WELL LOG:

Diameter of well, 18 inches.Total depth 503 ft. Depth of completed well 503 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

ft. to	ft. from	Material
0	2 1/2	soil
2 1/2	4	hardpan
4	16	clay & sand
16	27	green quick sand
27	43	green chalk
43	4871	sand & gravel
71	107	clay & sand
107	125	shale
125	144	green chalk
144	158	white sand & black gravel
158	364	green clay & streaks of sand
364	370	basalt sandstone
370	391	cinders, sand & gravel
391	406	red & gray sandstone
406	494	black shale
494	503	green clay

Ground elevation at well site _____ feet above mean sea level.

Work started 5,11 1959 Completed 5/31 1959

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME John A. VanMeter

(Person, firm, or corporation)

(Typed or printed)

Address Box 204 Malin, Oregon

Driller's well number _____

[Signed] John A. VanMeter (Well Driller)License No. 170 Dated 6/15, 1959



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.oregon.gov/owrd

Application for Well ID Number

Do not complete if the well already has a Well Identification Number.

RECEIVED

DEC 18 2020

I. OWNER INFORMATION

Current Owner Name (please print): Mike Peila

OWRD

Mailing Address: PO Box 537

City, State, Zip: Hines, OR 97738

Mail Well ID to: ☒ SAME AS ABOVE

☐ In Care Of (C/O)

Name & Address: _____

City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 24S (North / South) Range: 30E (East / West) Section: 24 SW 1/4 of the NE 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 2101 County Harney

GPS Coordinates: 43.47647544, 119.06677008

Street Address of Well, City: OR Hwy 31 (near)

If the property had a different street address in the past: _____

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation

Date Well Constructed (or property built): 5/31/59 Total Well Depth: 503 Casing Diameter: 18

Owner at time the well was constructed (if known): W.R. Clayton Well Report # (if known): HARN 841

Other Information: _____

SUBMITTED BY (please print): Denise A Montgomery, All Points Engr & Surveying

POB 767 Terrebonne

PHONE: 541-548-5833

EMAIL &/or FAX: neecee@apeands.com

97760

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

12-18-2020

Well Report Number:

HARN 841

Well Identification #:

L 140933