

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 3353/E-8

State Permit No. _____

(1) OWNER:

Name Richtron Financial Corp.
Address 2650 Washington Bld.
Ogden Utah

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
20" Diam. from 0 ft. to 20 ft. Gage 375
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " "
" " " " "

Ball test NO gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 24 in.
Diameter of well bore below seal 20 in.
Number of sacks of cement used in well seal _____ sacks
How was cement grout placed? _____

Was a drive shoe used? ☐ Yes ☒ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Harney Driller's well number _____
Section 8 T.33S R.31E W.M.

Bearing and distance from section or subdivision corner well is
in center of E1/2 Sec 8

(11) WATER LEVEL: Completed well.

Depth at which water was first found ft.

Static level ft. below land surface. Date _____

Artesian pressure lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 20"
Depth drilled 450 ft. Depth of completed well not completed ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	3	
Clay brown	3	15	
Sandstone brown med hard	15	42	
Sandstone red hard	42	71	
basalt brown med hard	71	95	
clay grey sticky	95	110	
basalt red med hard	110	121	
clay grey sticky	121	130	
Sandstone grey	130	170	
clay white (chalk like)	170	174	
Sandstone grey	174	200	
" Red	200	210	
" grey	210	220	
" Red	220	296	
clay blue green	296	400	
clay grey green with sand	400	430	
clay blue green with sand	430	450	
Temp. A daudered			

Work started 6/17 1978 Completed 1/10 1979

Date well drilling machine moved off of well 1/10 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Robert J. Osborn Date 1/30, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1100

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Osborn Drilling
(Person, firm or corporation) (Type or print)

Address 524 Rd 44 PASCO W.V.

[Signed] Robert J. Osborn
(Water Well Contractor)

Contractor's License No. 708 Date 1/30, 1979