

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED

State Permit No.

(1) OWNER:

Name Mr. Walter Kliner

Address 1725 - 89th. , N.E.
Bellevue, WA. 98004

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

16" Diam. from 0 ft. to 432 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Factory louvered

Size of perforations 1/8 in. by 2 1/2 in.
15, 120. perforations from 96 ft. to 432 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level.

Was a pump test made? ☒ Yes ☐ No If yes, by whom?

Yield: 620 gal./min. with 180 ft. drawdown after 8 hrs.

" " "
" " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 59 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used cement grout

Well sealed from land surface to 18 ft. ft.

Diameter of well bore to bottom of seal 29 in.

Diameter of well bore below seal 29 in.

Number of sacks of cement used in well seal 7 sack sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/8 in.

Gravel placed from 18 ft. to 620 ft.

(10) LOCATION OF WELL:

County Harney WATER RESOURCES DEPT. well number

n.e. 1/4 sec. 8 T. 24 R. 33-e W.M.

Bearing and distance from section or subdivision corner

312 ft. n.e. of center of the n.w. -
1/4 of sec. 8 t-24/ r-33-e

(11) WATER LEVEL: Completed well.

Depth at which water was first found 65 ft. ft.

Static level 8 ft. below land surface. Date 4/24/78

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 29"

Depth drilled 620 ft. Depth of completed well 432' ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
top soil	0	2	
sand	2	5	
blue & green clay	5	65	
gray sandstone	65	74	
sandy gray clay	74	93	
sandstone	93	95	
green sandy clay	95	145	
black clay	145	190	
gray & green clay	190	248	
black clay	248	284	
corase sand & med. gravel	284	290	
sand stringers of clay	290	307	
green claystone	307	329	
black cinders & sand	329	335	
gray sandstone	335	338	
soft sandstone & med sand	338	367	
gray clay sandstne strig	367	405	
coarse gay sand	405	408	
gray clay	408	440	

Work started 4/24/ 19 78 Completed 4/25/ 19 78

Date well drilling machine moved off of well 4/25/ 19 78

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] *Burdell J. Hauer* Date 4-25-78
(Drilling Machine Operator)

Drilling Machine Operator's License No. 10 26

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name *Western Water Wells Inc.*
(Person, firm or corporation) (Type or print)

Address 2485 W. Main St. Astoria, Ore.

[Signed] *James B. Smith*
(Water Well Contractor)

Contractor's License No. 659 Date 4/25/ 19 78



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for Well ID Number

RECEIVED

NOV 07 2016

WATER RESOURCES DEPT
SALEM, OREGON

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): CAMERON AND RACHEL KOEHN

Mailing Address: 67625 S. NEWTON RD

City, State, Zip: BURNS, OR 97720

Mail Well ID Tag to: ☒ SAME AS ABOVE ☐ In Care Of (C/O)

Name & Address: _____

City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 24S (North / South) Range: 33E (East / West) Section: 8 NE 1/4 of the NW 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 1901 County HARNEY

GPS Coordinates: 43 30' 16.31"N 118 40' 59.83"W

Street Address of Well, City: 67625 S NEWTON RD HARNEY COUNTY

If the property had a different street address in the past: _____

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Log, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): IRRIGATION

Date Well Constructed (or property built): 4-25-78 Total Well Depth: 432 Casing Diameter: 16"

Owner at time the well was constructed (if known): WALTER KLINER Well Log # (if known): HARN 985

Other Information: _____

SUBMITTED BY (please print): CHRIS SMITH

PHONE: 541-815-7417 EMAIL &/or FAX: smittyct@gmail.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

11-7-16

Well Log Number:

HARN 985

Well Identification #:

L-125009