

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 385/dw-24dd

State Permit No. _____

(1) OWNER:

Name Bruce Hanson

Address Talent
Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 47 1/2 ft. Gage 1250

" Diam. from _____ ft. to _____ ft. Gage _____

" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations _____ in. by _____ in.

_____ perforations from _____ ft. to _____ ft.

_____ perforations from _____ ft. to _____ ft.

_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

_____ gal./min. with _____ ft. drawdown after _____ hrs.

" " " " "

" " " " "

Ballor test 8 gal./min. with 6.0 ft. drawdown after 1 hrs.

_____ gal./min. with _____ ft. drawdown after _____ hrs.

_____ g.p.m. _____

Temperature of water 50 Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 46 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 17 sacks

How was cement grout placed? Pressure grouted

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? good depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Jackson Driller's well number _____

S.E. 1/4 S.E. 1/4 Section 24 T.38S. R. 2 W. W.M.

Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 76 ft.

Static level 68 ft. below land surface. Date 11-27-79

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 142 ft. Depth of completed well 138 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	2	—
Clay	2	7	—
Shale rock	7	12	—
Clay	12	38	—
Basalt (weathered)	38	40	—
Basalt (Drizzle 76')	40	85	—
" " Very hard	85	134	—
Basalt	134	140	—
Sand	140	142	—
RECEIVED			
DEC 31 1979			
WATER RESOURCES DEPT			
SALEM, OREGON			

Work started 11-13 1979 Completed 11-26 1979

Date well drilling machine moved off of well 11-27 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] E. J. Studabaker Date 11-26, 1979,
(Drilling Machine Operator)

Drilling Machine Operator's License No. 261

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name E. J. Studabaker
(Person, firm or corporation) (Type or print)

Address 55 W. Nevada St. - Ashland

[Signed] E. J. Studabaker
(Water Well Contractor)

Contractor's License No. 40 Date 11-26, 1979