

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

RECEIVED

SEP 20 1965 WATER WELL REPORT

STATE ENGINEER STATE OF OREGON (Please type or print)

State Well No. 39/16-3

State Permit No.

(1) OWNER:

Name Percy Lee
Address PI Box 495
Talent Ore.

(2) LOCATION OF WELL:

County Jackson Driller's well number 336
1/4 1/4 Section 3 T. 39 S. R. 14 W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 37 ft. Gage 25
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.
Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite
Depth of seal 37 ft. Was a packer used? no
Diameter of well bore to bottom of seal 6 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 87 ft. below land surface Date 9-14-65
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 4 1/2 gal./min. with 1 1/4 ft. drawdown after 1 hrs.

Artesian flow g.p.m. Date

Temperature of water 52 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 182 ft. Depth of completed well 182 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
soil clay small boulders red Bl.	0	2
clay soft boulders brown	2	19
" " " " " "	19	32
Chertstone? " " "	32	65
blue gray	45	62
Meda Sedimentary Blue Bl.	62	78
" " " " " "	78	105
" " " " " "	105	131
layers every few feet	105	131
Meda Sed. hard blue Bl.	131	149
" " " " " "	149	156
shist " " "	156	159
" " " " " "	159	182
with thin white layers making the mud grey		

Work started 9-7 1965 Completed 9-14 1965
Date well drilling machine moved off of well 9-14 1965

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME M.D. SHULTS well Drilling
(Person, firm or corporation) (Type or print)

Address 2034 W. main Medford

Drilling Machine Operator's License No. 94

[Signed] M.D. Shults
(Water Well Contractor)

Contractor's License No. 105 Date 9-14, 1965