

WATER WELL REPORT
STATE OF OREGON

RECEIVED

State Well No.

395/2w-8

DEC 18 1981

State Permit No.

WATER RESOURCES DEPT
SALEM, OREGON

(1) OWNER:

Name Bjorne Everson
Address 8730 Sterling Creek Rd.
City Jacksonville State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
Cased ☐ Bored ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED: Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from +1 ft. to 57 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Tested: gal./min. with ft. drawdown after hrs.
" " " "

Air test 3 1/2 gal./min. with drill stem at 400 ft. 1 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 6 sacks
How was cement grout placed? Pressure grouted

Was pump installed? ☐ No Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Jackson Driller's well number 63-81
1/4 1/4 Section 8 T. 39 R. 2WW W.M.
Tax Lot # 701 Lot Blk Subdivision
Address at well location: 8730 Sterling Creek Rd.
Jacksonville

(11) WATER LEVEL: Completed well.

Depth at which water was first found 98 ft.
Static level 50 ft. below land surface. Date 12-9-81
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6" "

Depth drilled 400 ft. Depth of completed well 400 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

	MATERIAL	From	To	SWL
Soil	Brown	0	2	
Sandstone	Brown	2	12	
Basalt	Brown	12	52	
Basalt	Grey	52	98	
Granite	Grey, broken	98	99	50
Granite	Grey	99	120	
Basalt	Grey	120	318	
Granite	Grey, broken	318	319	50
Granite	Grey	319	358	
Basalt	Grey	358	379	
Basalt	Grey with broken quartz	379	380	50
Basalt	Grey	380	400	

Work started 12-7-81 19 Completed 12-9 19 81
Date well drilling machine moved off of well 12-9 19 81

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] (Signature) Date 12-19 1981
(Drilling Machine Operator)

Drilling Machine Operator's License No. 785

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Crater Well Drilling, Inc.
(Person, firm or corporation) (Type or print)

Address 2870 Crater Lake Hwy. Medford

[Signed] (Signature)
(Water Well Contractor)

Contractor's License No. 687 Date 12-9 19 81

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690