

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the
STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT
STATE OF OREGON JAN 30 1968
(Please type or print)
(Do not write above this line)
STATE ENGINEER
SALEM OREGON
State Well No. 38/1-33
State Permit No.

(1) OWNER:

Name William A. Bickford
Address 1760 Eagle Mill Rd. Ashland Ore

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 1.6" ft. to 25 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in.	by	in.
perforations from		ft. to	ft.
perforations from		ft. to	ft.
perforations from		ft. to	ft.
perforations from		ft. to	ft.
perforations from		ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 10 ft. below land surface Date 1-27-68
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Field:	gal./min. with	ft. drawdown after	hrs.
"	"	"	"
"	"	"	"

Bailer test 15 gal./min. with 68 ft. drawdown after 2 hrs.

Artesian flow g.p.m. Date

Temperature of water 58 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Bentonite + cement
Depth of seal 25 ft.

Diameter of well bore to bottom of seal 7 1/2 in.

Were any loose strata cemented off? ☐ Yes ☒ No Depth

Was a drive shoe used? ☒ Yes ☐ No

Did any strata contain unusable water? ☒ Yes ☐ No

Type of water? Surface depth of strata 15 to 20'

Method of sealing strata off Casing + Bentonite

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Jackson Driller's well number 280
1/4 1/4 Section 33 T. 38S R. 1E W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 96 ft. Depth of completed well 96 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil Black adobe	0	5	
Clay dark Brown	5	8	
Clay Tan	8	10	
Clay, sand & Gravel med course & fine water	10	20	4
Sandstone Brown Hard	20	45	
Claystone Grey water			
at 45' 50' S.P.H.	45	48	10
Sandstone Grey Hard	48	75	
Claystone Grey	75	88	
Shale claystone dark			
Grey water 40 G.P.H.	88	92	10
Sandstone Grey Hard	92	96	
welded cap 1-27-68			

Work started 1-24 1968 Completed 1-27 1968

Date well drilling machine moved off of well 1-27 1968

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Mate-
rials used and information reported above are true to my best
knowledge and belief.

[Signed] Dallas S. DeLap Date 1-29, 1968
(Drilling Machine Operator)

Drilling Machine Operator's License No. 62

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

NAME Dallas S. DeLap Well Drilling
(Person, firm or corporation) (Type or print)

Address 749 Eagle Mill Rd Ashland Ore

[Signed] Dallas S. DeLap
(Water Well Contractor)

Contractor's License No. 36 Date 1-29, 1968