

20515

39E/1E-23

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.785)

MAR 17 1988

WATER RESOURCES DEPT. SALEM, OREGON

(1) OWNER: Name John Weisinger Address 3150 Siskiyou Blvd City Ashland State OR Zip 97502

(2) TYPE OF WORK: [X] New Well [] Deepen [] Recondition [] Abandon

(3) DRILL METHOD: [X] Rotary Air [] Rotary Mud [] Cable [] Other

(4) PROPOSED USE: [X] Domestic [] Community [] Industrial [] Irrigation [] Thermal [] Injection [] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No [] [X] Depth of Completed Well 161 ft. Explosives used [] [] Type Amount

Table with columns: HOLE Diameter, SEAL Material, Amount sacks or pounds. Row 1: 10, 0, 18, cement, 0, 18, 8 sacks. Row 2: 6, 18, 161.

How was seal placed: Method [] A [] B [X] C [] D [] E Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 6, +2, 18, .250, [X], [], [X], []. Liner: 4, -1, 161, .250, [], [X], [X], [].

Final location of shoe(s)

(7) PERFORATIONS/SCREENS: [X] Perforations Method skill saw [] Screens Type Material

Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Row 1: 100, 160, 6", 100, 1/8, [], [X].

(8) WELL TESTS: Minimum testing time is 1 hour [] Pump [] Bailer [X] Air [] Flowing Artesian Yield gal/min 100 Drawdown Drill stem at 160 Time 1 hr.

Temperature of water Depth Artesian Flow Found Was a water analysis done? [] Yes By whom Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County Jackson Latitude Longitude Township 39 N or S, Range 1e E or W, WM. Section 23 Tax Lot 2700 Lot Block Subdivision Street Address of Well (or nearest address) same

(10) STATIC WATER LEVEL: 24 ft. below land surface. Date 2-18-88 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 155, 156, 100, 24.

(12) WELL LOG: Table with columns: Material, From, To, SWL. Rows include: soil, red (0-3), clay, brown (3-5), sandstone, brown (5-11), green (11-31), brown (31-35), white (35-53), grey (53-62), blue (62-66), white (66-70), brown (70-71), white (71-155), blue, fractured (155-157), blue (157-161).

Date started 2-17-88 Completed 2-18-88

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief. Signed Frank Canode WWC Number 1432 Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief. Signed John Studebaker WWC Number 677 Date

RECEIVED

"START CARD"
NOTICE OF BEGINNING OF WELL CONSTRUCTION
(as required by ORS 537.762)

MAY - 6 1988
WATER RESOURCES DEPT.
SALEM, OREGON

This form must be completed, signed by both the owner (or authorized agent) and constructor, and the original delivered to the Water Resources Department prior to commencement of construction, alteration or abandonment of each well.

Owner's Name and Mailing Address John Weisinger
3150 SISKIYOU BLVD
Ashland, OR 97502

Proposed Commencement Date 2-17-88

Proposed Well Depth 200, Diameter 6"

and Use:

- Domestic
- Thermal
- Community
- Injection
- Industrial
- Other
- Irrigation

Proposed Well Location: County Jackson

Township 39 (N or S) Range 1E (E or W) Section 23

At least 2 of these must be provided

1. _____ 1/4 of _____ 1/4 of above section
2. street address of well location 3150 SISKIYOU BLVD
Ashland, OR
3. tax lot number of well location 2700
4. attach approved map with location identified.
(see reverse of this form for approved maps)

We hereby certify that we have read the back of this form, and that to the best of our knowledge the information provided herein is accurate and the well is being properly located from septic tanks and septic drain fields.

John Weisinger
Owner's Signature

x John Studabaker
Bonded Water Well Constructor

Owner
Title

License No. 679

2-17-88
Date

Company STUDEBAKER DRILLING, INC

Note: This is not a Water Right application. The owner is responsible for obtaining a Water Right through the Water Resources Department if required.