

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

State Well No. 3951E-24dd

State Permit No. _____

(1) OWNER:

Name Mr. Delmar Lloyd Payne
Address Ashland, Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cased ☒ Jetted ☐
Dig ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

6" Diam. from 0 ft. to 39 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations	in.	by	in.
perforations from		ft. to	ft.
perforations from		ft. to	ft.
perforations from		ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " "
" " " " "

per test 30+ gal./min. with 100 ft. drawdown after 1 hrs.

Artesian flow g.p.m. _____

Temperature of water 64 Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 37 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 20 sacks
How was cement grout placed? Pressure grouted

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? good depth of strata 250-440

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County X Jackson Driller's well number
SE 1/4 S.E. 1/4 Section 24 T. 39S. R. R. 1E. W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 250 ft.

Static level 32 ft. below land surface. Date 10-16-79.

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 451 ft. Depth of completed well 451 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	3	—
Clay	3	6	—
conglomerate rock	6	145	—
Shale rock	145	160	—
Conglomerate rock	160	250	—
" loose	250	251	32
" "	251	440	32
Shale rock	440	451	32

RECEIVED
OCT 24 1979

RECEIVED
JAN 30 1980
WATER RESOURCES DEPT
SALEM, OREGON

Work started 9-21 1979 Completed 10-15 1979.

Date well drilling machine moved off of well 10-16 1979.

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] E. J. Stuebelake Date 10-16, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 261

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name E. J. Stuebelake
(Person, firm or corporation) (Type or print)

Address 5520 Nevada St. - Ashland

[Signed] E. J. Stuebelake
(Water Well Contractor)

Contractor's License No. 40 Date 10-16, 1979.