

LEGISLATION

30066

395/2W/32cd

STATE OF OREGON

WATER WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT.

(START CARD) #

16246

SALEM, OREGON

MAY 04 1990

JACK

(1) OWNER:

Name Lee Smith Well Number: _____
Address 2354 Waters Church Rd
City Salem, Ore State Ore Zip 97330

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable

☐ Other _____

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 160' ft.

Explosives used ☐ Yes ☒ No ☐ Type _____ Amount _____

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks or pounds	
10"	0 30	Cement	0 30'	12 Sacs	
6"	30 160				

How was seal placed: Method ☐ A ☒ B ☒ C ☐ D ☐ E

☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	#1	29'		☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☐ Air ☐ Flowing ☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
8	160'	160'	1 hr.

Temperature of water _____ Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Clatsop Latitude _____ Longitude _____
Township 39 North Range 2 E or W M.
Section 32 3/4 SW 1/4
Tax Lot 206 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Same

(10) STATIC WATER LEVEL:

21' ft. below land surface.

Date 4-25-90

Artesian pressure _____ lb. per square inch.

Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found _____

From	To	Estimated Flow Rate	SWL
83'	84'	2	21'
126'	127'	2	21'
148'	149'	4	21'

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
Soil	0	1	
CLAY	1	6	
CLAYSTONE	6	14	
SANDSTONE	14	24	
SANDSTONE	24	53	
BASALT	53	83	
BASALT BROKEN	83	89	21
BASALT	89	126	
BASALT	126	127	21
BASALT	127	148	
BASALT BROKEN	148	149	21
BASALT	149	160	

Date started 4-25-90 Completed 4-25-90

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number _____

Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1457

Signed Evan Date 4-28-90