

STATE OF OREGON
WATER WELL REPORT
 (as required by ORS 537.765)

JACK
30270

AUG 9 1990

37S/1E/19

(START CARD) # 17516

(1) OWNER: Well Number: 6 six
 Name Robert G. Robertson
 Address 710 Gardley
 City Medford, Oregon State _____ Zip 97504

(2) TYPE OF WORK:
 New Well Deepen Recondition Abandon

(3) DRILL METHOD
 Air Rotary Mud Cable
 Other _____

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Other _____

(5) BORE HOLE CONSTRUCTION:
 Special Construction approval Yes No Yes No
 Depth of Completed Well 340 ft.
 Explosives used Yes No Type _____ Amount _____

HOLE			SEAL		Amount sacks or pounds	
Diameter	From	To	From	To		
10"	0	38'	cement	0	38'	15 sacks
6"	38'	340'				

How was seal placed: Method A B C D E
 Other _____
 Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+18"	38'	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 4"	-1	340'	.250	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 38'

(7) PERFORATIONS/SCREENS:
 Perforations Method skill saw
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
240'	340'	6"	120	1/8"	4"	<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump Bailer Air Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
15		339'	1 hr.

Temperature of water _____ Depth Artesian Flow Found _____
 Was a water analysis done? Yes By whom _____
 Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
 Depth of strata: _____

(9) LOCATION OF WELL by legal description:
 County Jackson Latitude _____ Longitude _____
 Township 37S N or S. Range 1E E or W, WM.
 Section 19 1/4 _____ 1/4 _____
 Tax Lot 500 Lot _____ Block _____ Subdivision _____
 Street Address of Well (or nearest address) Pine Ridge Drive

(10) STATIC WATER LEVEL:
80' ft. below land surface. Date 7-12-90
 Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
 Depth at which water was first found 280'

From	To	Estimated Flow Rate	SWL
280'	320'	15	80'

(12) WELL LOG: Ground elevation _____

Material	From	To	SWL
adobe	0	3	
clay, brown	3	14	
" , blue/grey	14	29	
claystone, grey	29	50	
" , brown/red	50	90	
" , grey	90	98	
" , brown	98	110	
" , brown/grey	110	120	
" , grey	120	130	
" , red	130	134	
" , grey	134	140	
" , red	140	160	
" , grey	160	170	
" , light brown	170	185	
" , grey, hard	185	240	
" , medium grey	240	280	
" , light grey	280	285	
" , blue grey	285	325	15
" , grey/green	325	340	

STUDEBAKER DRILLING, INC.
 1400 Arnold Lane
 Medford, Oregon 97501

Date started 7-16-90 Completed 7-17-90

(unbonded) Water Well Constructor Certification:
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
 Signed Frank Z. Conner WWC Number _____ Date _____

(bonded) Water Well Constructor Certification:
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
 Signed John Studabah WWC Number 1677 Date 6/8/90