

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT.
SALEM, OREGON (START CARD) #

355/34/6dc
32354

(1) OWNER: Well Number: 1
Name: KEN JOCHEN
Address: 8881 E. EVANS CREEK
City: ROGUE RIVER State: OR Zip: 97537

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well: 300 ft.
Explosives used ☐ Yes ☒ No ☐ Type: Amount:

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0	18	BENTONITE	0	18	500 lbs.
6"	18	300				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other: DRY POUR BENTONITE

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Casing:	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
	6"	+1	-75	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s): 75'

(7) PERFORATIONS/SCREENS:

☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing ☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
11 GPM	299		1 hr.

Temperature of water: 57° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes ☐ No By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County: JACKSON Latitude _____ Longitude _____
Township: 35 N or S, Range: 3 W E or W, WM.
Section: 6 SW 1/4 SE 1/4
Tax Lot: 700 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address): 12350 E. EVANS
ROGUE RIVER, OR 97537

(10) STATIC WATER LEVEL:

35 ft. below land surface. Date: 8-1-91
Artesian pressure _____ lb. per square inch. Date: _____

(11) WATER BEARING ZONES:

Depth at which water was first found		114	
From	To	Estimated Flow Rate	SWL
114	115	4 GPM	35
145	146	2 GPM	35
289	290	5 GPM	35

(12) WELL LOG:

Material	From	To	SWL
SOIL	0	5	
Brown Clay + Granite	5	19	
Brown Clay	19	27	
Gray Basalt	27	113	
Gray Basalt Fractured	113	115	35
Quartz fractures + Basalt	115	116	
Black Basalt	116	145	
Fractured Black Basalt	145	146	35
Gray Basalt with Quartz seams	146	200	
Black Basalt	200	256	
Black Basalt no change	256	289	
Fractured Black Basalt	289	290	35
Black Basalt	290	300	

Date started: 8-1-91 Completed: 8-2-91

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed: ADAM BOLLING WWC Number: 552
Date: 8-17-91