

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

JACK  
31955

(START CARD) #

31355

(1) OWNER:

Name CARL ROUCH Well Number: 1  
Address 3177 PLEASANT CK  
City ROGUE RIVER State OR. Zip 97537

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable  
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation  
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 180 ft.  
Explosives used ☐ ☒ Type \_\_\_\_\_ Amount \_\_\_\_\_

| HOLE     |         | SEAL      |         | Amount          |  |
|----------|---------|-----------|---------|-----------------|--|
| Diameter | From To | Material  | From To | sacks or pounds |  |
| 10       | 0 25    | BENTONITE | 0 25    | 850             |  |
| 10       | 25 38   | CEMENT    | 25 38   | 5 SACKS         |  |
| 6        | 38 180  |           |         |                 |  |

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E  
☒ Other DRY POUR 0-25/PAVED 25-38

Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

|         | Diameter | From | To  | Gauge | Steel                               | Plastic                  | Welded                              | Threaded                 |
|---------|----------|------|-----|-------|-------------------------------------|--------------------------|-------------------------------------|--------------------------|
| Casing: | 6        | +1   | -38 | 290   | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| Liner:  |          |      |     |       | <input type="checkbox"/>            | <input type="checkbox"/> | <input type="checkbox"/>            | <input type="checkbox"/> |

Final location of sheets: -38

(7) PERFORATIONS/SCREENS:

☐ Perforations Method \_\_\_\_\_  
☐ Screens Type \_\_\_\_\_ Material \_\_\_\_\_

| From | To | Slot size | Number | Diameter | Tele/pipe size | Casing                   | Liner                    |
|------|----|-----------|--------|----------|----------------|--------------------------|--------------------------|
|      |    |           |        |          |                | <input type="checkbox"/> | <input type="checkbox"/> |
|      |    |           |        |          |                | <input type="checkbox"/> | <input type="checkbox"/> |
|      |    |           |        |          |                | <input type="checkbox"/> | <input type="checkbox"/> |
|      |    |           |        |          |                | <input type="checkbox"/> | <input type="checkbox"/> |
|      |    |           |        |          |                | <input type="checkbox"/> | <input type="checkbox"/> |

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian

| Yield gal/min | Drawdown | Drill stem at | Time  |
|---------------|----------|---------------|-------|
| 12            |          | 178           | 1 hr. |
|               |          |               |       |
|               |          |               |       |

Temperature of water 57° Depth Artesian Flow Found \_\_\_\_\_

Was a water analysis done? ☐ Yes By whom \_\_\_\_\_

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other \_\_\_\_\_

Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:

County JACKSON Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 34 N or S. Range 4W E or W. WM. \_\_\_\_\_  
Section 33 NW 1/4 SE 1/4  
Tax Lot 813 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) 3177 PLEASANT CREEK RD - ROGUE RIVER OR

(10) STATIC WATER LEVEL:

31 ft. below land surface. Date 9/15  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:

| From | To  | Estimated Flow Rate | SWL |
|------|-----|---------------------|-----|
| 92   | 94  | 8                   | 31  |
| 129  | 130 | 3                   | 31  |
| 175  | 176 | 1                   | 31  |

(12) WELL LOG: Ground elevation 1000' PROX

| Material            | From | To  | SWL |
|---------------------|------|-----|-----|
| SOIL                | 0    | 2   |     |
| GRANITE W/CLAY      | 2    | 14  |     |
| DECOM. GRANITE      | 14   | 25  |     |
| DECOM. GRANITE HARD | 25   | 44  |     |
| GRANITE - HARD      | 44   | 92  |     |
| GRANITE - FRACTURED | 92   | 94  | 31  |
| GRANITE - HARD      | 94   | 129 |     |
| GRANITE - FRACTURED | 129  | 130 | 31  |
| GRANITE - HARD      | 130  | 175 |     |
| GRANITE - FRACTURED | 175  | 176 | 31  |
| GRANITE HARD        | 176  | 180 |     |

Date started 9-11-92 Completed 9-15-92

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed AQUA DRILLING WWC Number 1591  
Date 9-19-92

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed Robert R. Bushy WWC Number 552  
Date 9-19-92