

RECEIVED

STATE OF OREGON  
WATER WELL REPORT OCT - 2 1992  
(as required by ORS 537.765)

STUDEBAKER DRILLING, INC.  
1133 S. Riverside #16  
Medford, Oregon 97501

JACK 32S/2E/31  
1977  
(START CARD) # 44985  
3E

WATER RESOURCES DEPT.

(1) OWNER: SALEM, OREGON  
Name Pacific Power/Hydro Resources  
Address 920 S W Sixth Avenue 610PSB  
City Portland State Ore Zip 97204

(2) TYPE OF WORK:  
 New Well  Deepen  Recondition  Abandon

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 730 ft.  
Explosives used  Yes  No Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12	0	98	bentonite	0	25	12sacks
			chips	25	98	25sacks
8	98	730				

How was seal placed: Method  A  B  C  D  E  
 Other poured

Backfill placed from \_\_\_ ft. to \_\_\_ ft. Material  
Gravel placed from \_\_\_ ft. to \_\_\_ ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 12	+2	96	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 6	0	730	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 96

(7) PERFORATIONS/SCREENS:  
 Perforations Method torch  
 Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
420	730	6	60	1/8		<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
3 gpm		728	1 hr.

Temperature of Water 57 Depth Artesian Flow Found  
Was a water analysis done?  Yes By whom  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other  
Depth of strata:

(9) LOCATION OF WELL by legal description:  
County Jackson Latitude Longitude  
Township 32S N or S. Range 2E E or W. WM.  
Section 31 1/4 1/4  
Tax Lot 3 Lot Block Subdivision  
Street Address of Well (or nearest address) Crater Lake Hwy Prospect, Ore

(10) STATIC WATER LEVEL:  
140 ft. below land surface. Date 9/14/92  
Artesian pressure \_\_\_ lb. per square inch. Date

(11) WATER BEARING ZONES:  
Depth at which water was first found 420

From	To	Estimated Flow Rate	SWL
420	440	3	140

(12) WELL LOG:  
Ground elevation

Material	From	To	SWL
Shale, rock, fill, brown	0	2	
Rock, brown	2	42	
Rock, weathered, gray, black	42	61	
Clay, red	61	70	
Rock, soft, red	70	85	
Rock, hard, black	85	106	
Rock, volcanic, red	106	140	
Rock, volcanic, lavender	140	160	140
Rock, blue	160	198	
Lava, frosted, red	198	262	
Sandstone, brown	262	320	
Claystone, gray	320	341	
Lava, blue, gray	341	440	
Claystone, red	440	550	
Rock, volcanic, black	550	730	

Date started 9/8/92 Completed 9/14/92

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
Signed *Frank Canada* WWC Number 1432 Date 9/14/92

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
Signed *John Studabaker* WWC Number 679 Date 9/29/92



Oregon Water Resources Department  
 725 Summer Street NE, Suite A  
 Salem Oregon 97301  
 (503) 986-0900  
 www.oregon.gov/owrd

# Application for Well ID Number

RECEIVED

*Do not complete if the well already has a Well Identification Number.*

JUN 7 2023

OWRD

**I. OWNER INFORMATION**

Current Owner Name (please print): PacifiCorp  
 Mailing Address: 825 NE Multnomah St  
 City, State, Zip: Portland, OR 97232  
 Mail Well ID to:  SAME AS ABOVE  In Care Of (C/O)  
 Name & Address: Attn: Matt Jones 1111 Mill Creek Drive  
 City, State, Zip: Prospect, OR 97536

**II. WELL LOCATION INFORMATION** (Please fill out as completely as possible)

Township: 32 S (North / South) Range: 3 E (East / West) Section: 31 NW 1/4 of the SW 1/4  
 Tax Lot (usually last 3-5 numbers of Tax Map #): 101 County Jackson  
 GPS Coordinates: 42° 44' 29.3" N -122° 30' 53.4" W (42.741222, -122.51483333)  
 Street Address of Well, City: 1111 Mill Creek Dr, Prospect  
 If the property had a different street address in the past: \_\_\_\_\_

**III. GENERAL WELL INFORMATION** (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Domestic  
 Date Well Constructed (or property built): 9-14-92 Total Well Depth: 730' Casing Diameter: 12"  
 Owner at time the well was constructed (if known): PacifiCorp Well Report # (if known): JACK 31977  
 Other Information: \_\_\_\_\_

SUBMITTED BY (please print): Joseph Schmoll  
 PHONE: 541-858-4869 EMAIL &/or FAX: joseph.schmoll@pacificorp.com

To send the completed application, you may MAIL it to: Oregon Water Resources Dept. 725 Summer St NE, Suite A, Salem, Oregon 97301.  
 Or EMAIL the completed PDF form to: Ladeena.K.Ashley@water.oregon.gov, or FAX it to: (503) 986-0902.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

6-7-2023

Well Report Number:

JACK 31977

Well Identification #:

L-151806