

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

Jack  
33032

36S/4W/26  
51157

(START CARD) #

(1) OWNER: Ernest + Diane Fritchett  
Well Number \_\_\_\_\_  
Name Ernest + Diane Fritchett  
Address 1852 Fouts Crk Rd  
City Gold Hill State OR Zip 97525

(2) TYPE OF WORK:  
 New Well  Deepen  Recondition  Abandon

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 110 ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL		Material	Amount	
Diameter	From To	From	To		sacks	or pounds
10"	0 20			Bentonite	0 20	50 lb 12 SACKS
6"	+15 23			CASING	0 20	
6"	23 110			Open		

How was seal placed: Method  A  B  C  D  E  
 Other Bentonite

Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+15	23	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 23

(7) PERFORATIONS/SCREENS:  
 Perforations Method \_\_\_\_\_  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
3+	80'	Bottom	1 hr.

Temperature of Water 54° Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: 18'

(9) LOCATION OF WELL by legal description:  
County Jackson Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 36 N of S Range 4 E of W WM.  
Section 26 1/4 1/4  
Tax Lot 303 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) 3855 N. River Rd.  
Gold Hill, OR 97525

(10) STATIC WATER LEVEL:  
20 ft. below land surface. Date 4 Feb 94  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 25'

From	To	Estimated Flow Rate	SWL
25	30'	2	20
80	100	1	20

(12) WELL LOG:  
Ground elevation \_\_\_\_\_

Material	From	To	SWL
Red Clay & Gravel & Basalt	0	15	
Fractured Bed Rock w/ Red Clay	15'	18'	28
Basalt Bed Rock	18'	110	20
Broke Hydraulic Hose	36 gal		
	Cleaned up		
1 Cone of Tri Cone Twisted off Pushed To Side I Believe			
<b>RECEIVED</b>			
MAR 4 1994			
<b>RECEIVED</b>			
FEB 10 1994			
WATER RESOURCES DEPT. SALEM, OREGON			
WM. DIST. 14 GRANTS PASS, ORE			

Date started 22 Nov 93 Completed 8 Feb 94

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
Signed William [Signature] WWC Number 778  
Date 8 Feb 94