

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MEDINA WELL DRILLING

Instructions for completing this report are on the last page of this form.

RECEIVED

AUG - 4 1994

(START CARD) # 66539

(1) OWNER:

Name JOSEPH BERTO

Address 6539 ROGUE RIVER DR.

City SHADY COVE State OR. Zip 97539

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 200 ft.

Explosives used ☐ Yes ☒ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	36	CEMENT	0	36	11 SACKS
6"	36	200				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	37	.250	☒	☐	☒	☐
Liner: 4"	0	200	160	☐	☒	☐	☐

Final location of shoe(s) 37

(7) PERFORATIONS/SCREENS:

☒ Perforations Method SAW

☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
70	200	1/8X8	100			☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min Drawdown Drill stem at Time

9 GPM 200 1 hr.

Temperature of water 57 Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County JACKSON Latitude Longitude

Township 34S N or S Range 1W E or W. WM.

Section 16CA 1/4 1/4

Tax Lot 1401 Lot Block Subdivision

Street Address of Well (or nearest address) 6539 ROGUE RIVER

SHADY COVE, OR

(10) STATIC WATER LEVEL:

48 ft. below land surface.

Date 7-19-94

Artesian pressure lb. per square inch.

Date

(11) WATER BEARING ZONES:

Depth at which water was first found 85

From	To	Estimated Flow Rate	SWL
85	179	9 GPM	48

(12) WELL LOG:

Ground Elevation

Material	From	To	SWL
SOIL, BROWN	0	1	
CONGLOMERATE, BROWN	1	24	
CLAYSTONE, BROWN	24	30	
CLAYSTONE, GREY, SOFT	30	200	48

MEDINA WELL DRILLING
3286 Hanley Road
Central Point, OR 97502
(503) 664-6339

Date started 7-19-94

Completed 7-19-94

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed

Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1207

Signed

Date 7-19-94