

WATER WELL REPORT
STATE OF OREGON

State Well No.

35S/2W-11Ab

State Permit No.

(1) OWNER:

Name Tom Sugden
Address 16083 Antioch Rd,
City Central Point, Oregon State 97502

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
☐ Bored ☐ Thermal: Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☐ Plastic ☒
Threaded ☐ Welded ☐

6" Diam. from 0 ft. to 60 ft. Gauge 160 class
" Diam. from ft. to ft. Gauge

(6) LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

Air test 180 gal./min. with drill stem at 240 ft. 1 1/2 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 56 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used cement
Well sealed from land surface to 40 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 13 sacks
How was cement grout placed? pressure pumped

Was pump installed? no Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Jackson Driller's well number 120
nw 1/4 SE 1/4 Section 11 T. 35S R. 2W W.M.
Tax Lot # Lot Blk Subdivision
Address at well location: same as 1

(11) WATER LEVEL: Completed well.

Depth at which water was first found 228 ft.
Static level 25 ft. below land surface. Date 10-17
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 240 ft. Depth of completed well 240 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
soil brown	0	6	
soil & clay brown	6	19	
sandstone blue hard	19	53	
sandstone brown soft	53	54	
sandstone blue hard	54	206	
granite green hard	206	218	
sandstone blue hard	218	240	25

RECEIVED

NOV 17 1981

WATER RESOURCES DEPT
SALEM, OREGON

Work started 10-17 1981 Completed 10-17 1981
Date well drilling machine moved off of well 10-17 1981

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] *John Quinn* Date 10-20, 1981
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1242

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Gribble Well Drilling
(Person, firm or corporation) (Type or print)

Address 195 Country Lane Gold Hill, Oregon 97525

[Signed] *Lyj Mulken*
(Water Well Contractor)

Contractor's License No. 705 Date 10-20, 1981

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690