

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

STATE OF OREGON
(Please type or print)

(Do not write above this line)

RECEIVED

State Well No. 333/2W-11

SEP 7 1976

State Permit No.

(1) OWNER:

Name Phil Cook

Address 2560 Cedar Lane,
Medford, Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 21 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Model No.

Type
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

AIR

Bailer test 55 gal./min. with 108 ft. drawdown after 1 1/2 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 3 sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Jackson Driller's well number

1/4 Section 11 T. 35 R. 2W W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 110 ft.

Static level 56 ft. below land surface. Date 8/31/76

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 164 ft. Depth of completed well 164 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil--brown	0	2	
Sandstone--brown	2	12	
Sandstone--gray	12	60	
Claystone--black	60	66	
Sandstone--gray	66	140	
Sandstone--gray	66	140	
Claystone--white	140	144	
Sandstone--white	144	150	
Sandstone--brown	150	154	
Sandstone--gray	154	164	

Work started 8/30 19 76 Completed 8/31 19 76

Date well drilling machine moved off of well 8/31 19 76

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] *Wayne Milkowski* Date 9/3, 1976
(Drilling Machine Operator) 483

Drilling Machine Operator's License No.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Virgle Gribble Well Drilling
(Person, firm or corporation) (Type or print)

Address 8380 Ramsey Rd. Gold Hill, Ore.

[Signed] *Wayne Milkowski*
(Water Well Contractor)

Contractor's License No. 461 Date 8/31, 1976

(USE ADDITIONAL SHEETS IF NECESSARY)

SP*45658-119